



SMEC INTERNAL REF. 30034151-RPT-3.7-001

Geotechnical Factual Report

Bundaberg East Levee

Reference No. 30034151-RPT-3.7-001

Prepared for Department of Housing, Local Government, Planning and Public Works

22 May 2024

Document Control

Document	Geotechnical Factual Report
File Location	\\filer.nasuni.local\SMEECANZ\Projects\300341\30034151 - Bundaberg\100 Prelim Design\Geotechnical\PD01 Geotech Investigation\09 RPT\02 Factual
Project Name	Bundaberg East Levee
Project Number	30034151-RPT-3.7-001
Revision Number	0

Revision History

Revision No.	Date	Prepared By	Reviewed By	Approved for Issue By
0	22/05/2024	Boung Yoon	Nicholas Alexander	Matt Box

Issue Register

Distribution List	Date Issued	Number of Copies
Department of Housing, Local Government, Planning and Public Works	22/05/2024	1

SMEC Company Details

Approved by	Matt Box		
Address	Level 6, 480 St Pauls Tce, Fortitude Valley, QLD, 4006, Australia		
Telephone	+61 478 669 452		
Email	Matt.Box@smec.com	Website	www.smec.com

The information within this document is and shall remain the property of:

Queensland Department of Housing, Local Government, Planning and Public Works

Important Notice

This report is confidential and is provided solely for the purposes of detailing the Geotechnical Investigation Factual Information for the Bundaberg East Levee (BEL) Project. This report is provided pursuant to a Consultancy Agreement between SMEC Australia Pty Limited ("SMEC") and Department of Housing, Local Government, Planning and Public Works, under which SMEC undertook to perform a specific and limited task for the Department of Housing, Local Government, Planning and Public Works. This report is strictly limited to the matters stated in it and subject to the various assumptions, qualifications and limitations in it and does not apply by implication to other matters. SMEC makes no representation that the scope, assumptions, qualifications and exclusions set out in this report will be suitable or sufficient for other purposes nor that the content of the report covers all matters which you may regard as material for your purposes.

This report must be read as a whole. The executive summary is not a substitute for this. Any subsequent report must be read in conjunction with this report.

The report supersedes all previous draft or interim reports, whether written or presented orally, before the date of this report. This report has not and will not be updated for events or transactions occurring after the date of the report or any other matters which might have a material effect on its contents, or which come to light after the date of the report. SMEC is not obliged to inform you of any such event, transaction or matter nor to update the report for anything that occurs, or of which SMEC becomes aware, after the date of this report.

Unless expressly agreed otherwise in writing, SMEC does not accept a duty of care or any other legal responsibility whatsoever in relation to this report, or any related enquiries, advice or other work, nor does SMEC make any representation in connection with this report, to any person other than Department of Housing, Local Government, Planning and Public Works. Any other person who receives a draft or a copy of this report (or any part of it) or discusses it (or any part of it) or any related matter with SMEC, does so on the basis that he or she acknowledges and accepts that he or she may not rely on this report nor on any related information or advice given by SMEC for any purpose whatsoever.

Contents

1	Introduction	6
1.1	Project Background	6
1.2	Purpose of this Report.....	7
1.3	Report Scope and Structure.....	7
2	Site Description	8
3	Geology and Topography	10
3.1	Geology.....	10
3.2	Topography	11
4	Geotechnical Site Investigation	12
4.1	Scope of the Work	12
4.2	Method of Investigation	12
4.3	Health and Safety	12
4.4	Environmental and Cultural Heritage.....	12
4.5	Underground Service and Utilities.....	13
4.6	Traffic Management	13
4.7	Phase 1 - Intrusive Site Investigations	13
4.7.1	Boreholes.....	13
4.7.2	Piezocone Penetration Testing (CPTu)	14
4.8	Phase 2 - Non-Intrusive Site Investigation	15
4.9	Laboratory Testing	15
5	Geotechnical Investigation Results.....	17
5.1	Subsurface and Groundwater Conditions.....	17
5.2	In Situ Testing	18
5.2.1	Standard Penetration Testing (SPT)	18
5.2.2	Pore Pressure Dissipation Testing (PPDT).....	18
5.2.3	Vane Shear Testing	18
5.2.4	Falling Head Percolation Testing.....	19
5.3	Laboratory Testing	20
6	Limitations and Assumptions	21
6.1	General	21
6.2	Notes Relating to Geotechnical Factual Reports.....	21
6.3	Unforeseen Conditions.....	21
6.4	Subsurface Information	22

Appendices

Appendix A	As built Geotechnical Investigation Plan	23
Appendix B	Explanatory Notes and Borehole Logs	24
Appendix C	SPT Photographs	25
Appendix D	Piezocone Penetration Test	26
Appendix E	Pore Pressure Dissipation Test.....	27
Appendix F	Vane Shear Test.....	28
Appendix G	Geophysics Survey	29
Appendix H	Laboratory Test Certificates	30

List of Tables

Table 3-1: Published Descriptions of Geological Formations present within the Site Area	10
Table 4-1: As built Borehole Investigation Details	14
Table 4-2: As built CPT Investigation Details	15
Table 4-3: Soil Laboratory Testing Schedule	16
Table 5-1: PPDT results	18
Table 5-2: Vane shear test results.....	18

1 Introduction

1.1 Project Background

In January 2013 ex-Tropical Cyclone Oswald caused devastating flooding to Bundaberg and surrounding regions. The Burnett River peaked at +9.53m (AHD) at the Targo Street gauge in the Bundaberg CBD. This was a record level for Bundaberg. Significant inundation of commercial and residential property in Bundaberg North, Bundaberg South (including the CBD) and Bundaberg East occurred.

Following the flood event, Bundaberg Regional Council (BRC) and the State Government undertook consultation with the Bundaberg community and independent experts to identify potential works that could provide flood mitigation solutions for the people of Bundaberg, their homes, businesses and the local economy.

In 2019, a Business Case was finalised for the BEL project. This included a levee concept design, founded on flood studies (hydrological and hydraulic), geotechnical investigations, desktop studies and community engagement. The primary aim of the levee is to reduce the impacts of flooding from the Burnett River on Bundaberg East and Bundaberg South.

The Bundaberg East Levee (BEL) design will feature approximately 1.6 kilometres of levee near the Burnett River's southern bank, a flood gate and pump station at the outlets of both Saltwater Creek and the unnamed "Distillery Creek." These floodgates will be closed during regional flood events to prevent backwater flooding from the Burnett River, safeguarding the Bundaberg CBD and East/South Bundaberg areas. This system is designed to protect against a flood event comparable to the 2013 event, with approximately 150mm of freeboard.




Figure 1-1: Locality Plan of Project Site

1.2 Purpose of this Report

SMEC Australia Pty Ltd (SMEC) has been commissioned by the Queensland Department of Housing, Local Government Planning and Public Works (DHLGPPW) to undertake the Preliminary design of a flood levee wall, large flood gates and pump stations to protect East Bundaberg from flooding. As part of the Preliminary Design phase, SMEC is required to carry out geotechnical investigation in two phases to collect adequate geological / geotechnical data for the Detailed Design Stage for the geotechnical aspects of the project comprising:

- Phase 1 – Intrusive geotechnical site investigation
- Phase 2 – Non-intrusive investigation using geophysics

The purpose of this Report is to document details on the geotechnical investigation carried out up to date, including the details of the field work, in situ testing and laboratory testing.

1.3 Report Scope and Structure

The scope of geotechnical investigation works covered in this Report includes:

- Synopsis of the overall investigations
- Description of the site conditions, geology and topography
- Summary of fieldwork
- Summary of in situ and laboratory tests undertaken
- Laboratory testing certificates
- Engineering logs of boreholes
- As-built investigation layout plan(s)
- Site photographs
- Photographs of soil samples

2 Site Description

The BEL Project site is located in a commercial, residential and mixed-use area adjacent to the southern bank of the Burnett River in Bundaberg, Queensland. The Bundaberg East Levee will run parallel to the southern bank of the Burnett River and across Saltwater Creek and Distillery Creek. The levee will consist of two segments i.e. the City Levee Alignment and the Distillery Levee Alignment as shown in Figure 2-1.




Figure 2-1: Location Plan of Project Site

The City Levee alignment is located in the south-western section of the project site, bounded by Quay Street to the south, pedestrian footpath and crossing over the Saltwater Creek and Scotland Street to the south, Peterson Street to the east, and the Burnett River to the north. Large flood gate and pump station structures will be constructed at the Saltwater Creek crossing and connected to the levee at both sides of the structures i.e. Rowing Club and 1E Quay Street. The City Levee length approximates around 1000m.

The Bundaberg Rowing Club and carpark are situated in the low-lying area near the Saltwater Creek and bounded by the existing block wall (approximately 3m high) and concrete footpath connecting to the 1E Quay Street through the existing pedestrian bridge. The 1E Quay Street area is located in a relatively elevated area and covered by grass. Significant slope instability due to toe scouring of the southern riverbank during a flood event were reported by Bundaberg Regional Council (BRC) in this area. The area from Quay Street to Peterson Street is used for commercial and residential purposes and located generally flat ground with some elevation. Overhead power lines are present along the Quay Street in close proximity to the proposed levee alignment.



Figure 2-2: City Levee Alignment Site

The Distillery Levee alignment is located in the north-eastern section of the site, bounded by Crane Street to the south, crossing over the unnamed creek near the distillery (Distillery Creek) and the Bundaberg Sugar Mill site to the east and the Burnett River to the north. The flood gate will be constructed parallel to the existing bridge at the Distillery Creek crossing and connected to the levee at both side of the structures i.e. northern end of Cran Street and south-west of Bundaberg Sugar Mill site. The Distillery Levee length is approximately 570 m.

Cran Street is connected to the Distillery Creek bridge entering into the Bundaberg Sugar Mill (BSM) site. Various sized boulders and rock blocks were observed in the creek bed with an evidence of scour at the bridge approach embankments. The proposed alignment within the BSM site is generally located in a grassed area until it starts running parallel to the southern bank of the Burnett River.



Figure 2-3: Distillery Levee Alignment Site

3 Geology and Topography

3.1 Geology

The State of Queensland Department of Natural Resources and Mines, GeoResGlobe Version 2.14 (2022) indicates that the project site is situated within areas of Quaternary age alluvial deposits (listed as a mixture of clay, silt, sand and gravel with local coarse cobbles and boulders), and of Eocene - Miocene age sedimentary rocks of the Elliot Formation (sandstone, conglomerate, mudstone, siltstone, and shale).

The Elliot Formation is a significant geological unit in the Bundaberg region and generally experienced periods of deep weathering during Cenozoic Era, resulting in distinct features including reddish-brown colour, mottling, iron-oxide rich patches and a unique duricrust appearance, and zones of increased permeability. The formation typically comprises of a few meters of moderate plasticity clays above a weakly cemented sandstone cap overlying a 20 m to 30 m thick gravelly and clayey sand layer. The top of bedrock is typically encountered at a depth of around 60 m below existing ground surface in the vicinity of Saltwater Creek (based on an advice from a local drilling contractor).

The published surface geology of the project site is shown in Figure 3–1, and the published descriptions of the corresponding geological formations are provided in Table 3–1.



Figure 3–1: Published Geology of the Project Site

Table 3–1: Published Descriptions of Geological Formations present within the Site Area

Label	Unit	Age	Description
Te	Elliot Formation	Eocene - Miocene	Sedimentary Rock - Quartzose to sublabele sandstone, conglomerate, siltstone, mudstone, shale
Qa-QLD	Alluvium	Quaternary	Clay, silt, sand and gravel; flood-plain alluvium

3.2 Topography

The topography of the project site comprises a relatively flat, occasionally undulating terrain with meandering creeks. The ground surface elevation excluding creek channels generally ranges from between approximately 2 m Australian Height Datum (AHD) to 11 m AHD across the site.

Dense vegetation comprising mangroves and marine plants is generally present in low-lying areas located along the Burnett River and the Saltwater Creek. A historical road bridge crossing the Saltwater Creek at Daphne Geddes park is situated between Quay Street and Bourbong Street near Kendall Flat sport ground. Settling ponds are located in the north-eastern side of Cran Street and within the Bundaberg Sugar Ltd site.

The published topography map for the Bundaberg East area is provided in Figure 3–2.



Figure 3–2: Published Topography of the Project Site

4 Geotechnical Site Investigation

4.1 Scope of the Work

The scope of the Geotechnical Site Investigation work to be undertaken at the preliminary design (PD) stage including:

- **Phase 1 - Intrusive site investigation** comprising drilling boreholes to log the soil and rock strata, piezo-cone penetration testing (CPTu) with pore pressure dissipation and vane shear tests, in-situ permeability testing (focusing on existing fill layers), disturbed and undisturbed soil sampling and a suite of laboratory tests.
- **Phase 2 - Non-intrusive site Investigation** comprising underwater and land-based seismic refraction survey within the footprint of the flood gate and pump station structures at Saltwater Creek and levee alignments along the Quay Street and Cran Street.

The results of the geotechnical investigation will be used to characterise site specific subsurface conditions and to establish representative ground models with geotechnical design parameters for detailed design for the levee embankment/wall, flood gate and pump station structures.

4.2 Method of Investigation

The standards and specifications adopted in developing the scope for the geotechnical investigation are:

- AS1726 (2017) Geotechnical Site Investigations
- AS1289 Testing of Soils for Engineering Purposes
- Department of Transport and Main Roads (DTMR) Geotechnical Design Standard – Minimum Requirements.

4.3 Health and Safety

The investigation was performance under a Health and Safety Management Plan (HSMP) prepared by SMEC. The HSMP helps ensure compliance with applicable legislation, regulation, company policies and procedures. investigation Contractors provided training and competency records for personnel involved in the investigation and evidence of any operational and documented workplace health and safety policies in conformance with the Workplace Health and Safety Act, Regulations and Codes of Practice. Task specific Safe Work Method Statements (SWMS) detailing all site activities and associated hazard identification and mitigation were provided to the DHLGPPW prior to commencement of the investigation.

4.4 Environmental and Cultural Heritage

Geotechnical investigation was carried out with regard to DHLGPPW requirements and relevant state and federal environmental and cultural heritage regulations. Mitigation measures implemented as part of the site investigation involved:

- Assessment of the location and extent of any vegetation clearance requirement during a site walkover prior to the commencement of any investigation work. Based on the assessment, no vegetation clearance was conducted at proposed investigation locations.
- Reducing the actual ground disturbance footprint at investigation sites as much as practicable.
- Where any environmental or cultural heritage issues, e.g. marine plants, threatened/ endangered plant species, fauna habitat, the existing historical pedestrian bridge etc., were identified, these locations were avoided from the investigation in consultation with a SMEC environmental team on site.

- Actual borehole and CPT locations were relocated outside the influence zone of Environmental and Cultural Heritage during a site walkover.
- Heavy duty ground protection mats were used to minimise any disturbance if necessary.
- Drilling mud (comprising biodegradable drilling fluid and fine drill cuttings) was disposed of off-site by using an approved method at completion of drilling.
- Health, Safety and Environmental and Cultural Heritage Management Plan relevant to this investigation was submitted to the Client prior to the commencement of any investigation work.

4.5 Underground Service and Utilities

Prior to commencement of the proposed field works, all proposed investigation locations were checked for underground services using a Before You Dig Australia (BYDA) and accredited service locator. Service locating was also undertaken via electronic wand and ground penetrating radar (GPR). The final borehole and CPT locations were set out with a safe distance away from any identified services.

4.6 Traffic Management

Minor traffic control was provided to ensure safety of workers and public during daytime hours for the investigation works. The traffic management plan was subject to change following receipt of the traffic management permit and traffic guidance scheme (TGS) prepared by the traffic management subcontractor depending on the specific requirements of the permit.

4.7 Phase 1 - Intrusive Site Investigations

4.7.1 Boreholes

As part of the Phase 1 investigation, drilling of nine (9) boreholes (designated BH01 to BH06 and BH08 to BH10) was completed under the supervision of a SMEC Geotechnical Engineer from 17 April to 29 April 2024.

The boreholes were advanced using a Comacchio Geo 405 drilling rig using solid flight auger and rotary wash boring techniques in soil material until practical refusal or nominated target depth was achieved. In situ testing comprised standard penetration tests (SPTs) at typical spacing of either 1 m or 1.5 m based the observed material type. Pocket penetrometer readings in cohesive materials were conducted. On completion of drilling, the boreholes were backfilled with a cementitious and bentonite grout mixture to match existing surface levels.

Each SPT sample was inspected, logged and photographed on-site, then placed in a sample bag and correctly labelled for further laboratory testing if required. Relatively undisturbed soil samples were collected using 90mm diameter thin-walled (U90) tubes which were labelled, inspected, logged and immediately sealed on site.

Open standpipes were installed at three (3) borehole locations to monitor variation in groundwater level with time. Falling head percolation testing was also carried out within the surficial fill or natural soil layers to a depth of 2.5m below ground surface at four (4) borehole locations.

All disturbed or undisturbed soil samples were transported to laboratories to carry out soil testing.

The location of each borehole was surveyed by a registered surveyor after completion of investigation works.

All geotechnical investigations were carried out in the full-time presence of a qualified and suitably experienced geotechnical professionals in accordance with the relevant sections of AS1726 – Geotechnical Site Investigation

The borehole investigation locations are detailed in Table 4-1.

Engineering logs of each borehole and explanatory notes are presented in Appendix B, and SPT photographs are shown in Appendix C.

Table 4-1: As built Borehole Investigation Details

Bore ID	Location	Coordinates		Surface Level (m AHD)	Terminated Depth (m)	Target Structure	Remark
		Easting	Northing				
BH01	Quay Street	435335.68	7250162.02	4.28	20.75	Levee	Relocated due to overhead power lines
BH02	Rowing Club	435018.32	7250106.63	5.03	22.95	Levee and flood gate / pump station	Relocated due to refusal within rock and boulder fills at 1m BGL. Terminated due to refusal at new location
BH03(*)	Quay Street	435577.61	7250229.57	3.79	25.45	Levee	Relocated due to refusal within rock and boulder fills at 1m BGL. Terminated due to hammer bounce at new location
BH04(*)	1E Quay Street	435089.96	7250122.78	7.25	25.10	Levee and flood gate / pump station	Terminated due to hammer bounce
BH05	1E Quay Street	435062.03	7250140.03	6.66	25.10	Levee and flood gate / pump station	Terminated due to hammer bounce
BH06	Intersection between Scotland St and Petersen St	435707.86	7250276.28	8.98	16.95	Levee	-
BH07	Distillery Creek	435855.22	7250566.56	5.70	-	Levee and flood gate	Unable to do service locating
BH08(*)	Distillery Creek	435793.39	7250636.95	5.81	29.95	Levee and flood gate	-
BH09	Sugar Mill site	435797.51	7250732.49	8.15	19.95	Levee	-
BH10	Sugar Mill site	435335.68	7250162.02	4.89	19.95	Levee	-

Notes:

1. BGL: Blow Ground Level
- 2.
3. (*) Standpipe installation

4.7.2 Piezocone Penetration Testing (CPTu)

Six (6) piezocone penetration tests (CPTu) were carried out at the locations shown in Table 4-1, focusing on the soft soil area identified in available geotechnical information (Concept Engineering Report, 2019). Soil type and engineering characteristics of soft soils such as shear strength, deformation and consolidation characteristics, and permeability will be assessed based on interpretation of CPTu results. The following requirements for CPTu tests were considered:

- CPTu testing to be undertaken with pore water pressure measurement for the full depth.
- Pore Pressure Dissipation testing (PPDT) to be undertaken for a duration adequate for reaching 50% of the initial excess pore water pressure or to a state of equilibrium.

- Pore pressure dissipation test at selected locations.
- In situ vane shear testing to be undertaken at selected locations.

The output of CPTu, PPDT and vane shear testing are presented in Appendix D to Appendix F.

Table 4–2: As built CPT Investigation Details

Borehole ID	Location	Coordinates		Target Depth (m)	Target Structure	Remark
		Easting	Northing			
CPT01	Rowing Club	435019.19	7250106.66	15.49	Levee and flood gate / pump station	Pore pressure dissipation / vane shear testing
CPT02	1E Quay Street	435098.92	7250145.12	24.26	Levee and flood gate / pump station	Pore pressure dissipation / vane shear testing
CPT03	1E Quay Street	435168.12	7250146.11	23.18	Levee	Pore pressure dissipation testing
CPT04	Quay St	435213.89	7250124.52	29.48	Levee	Relocated due to overhead power lines
CPT05	Quay St	435335.19	7250159.99	20.22	Levee	Pore pressure dissipation / vane shear testing
CPT06	Sugar Mill site	435818.04	7250601.51	26.43	Levee	Pore pressure dissipation testing

Notes:

1. BGL: Below Ground Level

4.8 Phase 2 - Non-Intrusive Site Investigation

Underwater and land-based geophysics survey was performed using seismic refraction method to assess subsurface profile along the proposed alignment under the supervision of a SMEC Geotechnical Engineer from 13 May to 14 May 2024.

Underwater seismic refraction survey was carried out using a vessel connecting source of shock waves and hydrophone array as receivers to calculate seismic velocities and layer depths within the footprint of flood gate structure at Saltwater Creek. Land-based seismic refraction survey was also carried out at both banks of Saltwater Creek, along the Quay Street and Cran Street. An accelerated weight drop was utilised as the seismic energy source to assist the achieve a certain depth of penetration below ground level.

Actual depth of penetration of the investigation will be limited by the signal strength provided by the seismic source, the geometry of the source positions and the geophone array and the geological conditions. The fieldwork was undertaken by engineers or scientists from SMEC subcontractor under the supervision of a SMEC site representative.

Output of geophysics survey will be updated in Appendix F for the next submission.

4.9 Laboratory Testing

Laboratory testing was conducted by a NATA Accredited Laboratory in accordance with applicable Australian or DTMR Standards including:

- AS1289 - Methods of Testing Soils for Engineering Purposes

- AS4133 – Methods of Testing Rocks for Engineering Purposes
- DTMR Materials Testing Manual, Edition 5, Amendment 6

Soil laboratory testing conducted by Trilab and CMT Laboratory based in Brisbane. The laboratory testing schedule is summarised in Table 4–3.

Table 4–3: Soil Laboratory Testing Schedule

Test Description	Quantity	Test Methods
Particle Size Distribution	18	AS1289 3.6.1 & 3.6.3
Atterberg Limits and Linear Shrinkage	25	AS1289.3.9.1, 3.9.2, 3.2.1, 3.4.1
Moisture Content	22	AS1289.2.1.1, 2.1.2, 2.1.4, 2.1.5, 2.16, 5.8.1
Emerson Class	5	AS1289 3.8.1
Oedometer	5	AS1289.6.6.1
Consolidation Undrained Triaxial Test with pore water pressure measurement	5	AS 1289.6.4.2
Falling or Constant Head Permeability	3	AS1289.6.7.2
Organic Content	5	AS1289.4.1.1
Standard compaction	3	AS1289.5.1.1
California Bearing Ratio with swell measurement (4 days soaked)	3	AS1289.6.1.1
Soil aggressivity Suite (pH, EC, chloride, sulphate, Major Cations/Anions, Total Acidity)	21	AS 1289.4.2.1, 4.3.1, Q130A, Q130B and Q131B

5 Geotechnical Investigation Results

5.1 Subsurface and Groundwater Conditions

The subsurface conditions encountered across the proposed project site generally comprises surficial layers of granular or cohesive fill underlain by alluvial soils, which in-turn, overly the Elliott Formation. This can be summarised as follows:

- Fill was encountered from the ground surface in six (6) boreholes to various depths between 1.6m and 4.5m below ground surface, comprising of silty/clayey sand or sandy/silty clay.
- Alluvial soils were generally encountered at various depths across the project site, comprising loose silty sand, very soft to soft silty clay, sandy clay or clay of dark grey colour. The alluvial soils present in an upwards fining sequence. Some gravels are present adjacent to Saltwater Creek and near the Distillery which are overlain by progressively finer grained materials. Highly compressible marine clay was encountered with thickness ranging from 4 m to 12 m.
- Elliott Formation (inferred residual soils) were encountered below alluvial soils in all boreholes, comprising of medium dense to dense silty/clayey sand with some gravels or stiff to hard sandy/silty clay. The formation was generally encountered at deep depths i.e. > 10 m near the Saltwater Creek and the Distillery Creek. Hard indurated / cemented gravel, sand and clay layers were possibly in localised areas, likely resulting in auger and rock roller bits refusal during drilling holes. Bedrock was not encountered.

Standing water levels were measured with a frequency of twice a day in the standpipe piezometers installed in BH03, BH04 and BH08 during the investigation period. The observed groundwater levels are summarised in Figure 5-1.




Figure 5-1: Groundwater Level Variation

5.2 In Situ Testing

5.2.1 Standard Penetration Testing (SPT)

Standard Penetration Tests (SPT) were carried out during the drilling of each of the boreholes. Retrieved SPT samples were logged and photographed by experienced geotechnical personnel. SPT results are presented on the boreholes logs in Appendix B along with photographs in Appendix C.

5.2.2 Pore Pressure Dissipation Testing (PPDT)

Pore pressure dissipation testing (PPDT) was carried out in fine grained materials to estimate field permeability of soft clays during the investigation of CPT01, CPT02, CPT03, CPT05 and CPT06. Output of PPDT is presented in Appendix E.

Table 5-1: PPDT results

Test ID	Depth (m)	Material Type	Origin	Peak Pore Pressure (kPa)	Final Pore Pressure (kPa)	Time for 50% dissipation (min)
CPT01	6.5	CLAY	Alluvium	286.5	141.6	83.1
	10.5	CLAY	Alluvium	468.5	129.2	128.8
CPT02	8.5	CLAY	Alluvium	303.8	154.3	45
	14	CLAY	Alluvium	521.7	300.6	185.6
	19.4	Silty CLAY / Sandy SILT	Elliot Formation	1231.5	140.0	0.89
CPT03	7	CLAY	Alluvium	209.4	110.1	145
	15	CLAY	Alluvium	504.9	154.3	149.8
	17.49	Silty CLAY / Silty SAND	Elliot Formation	623.8	127.6	0.87
CPT05	9.2	CLAY	Alluvium	251	99.7	369.3
CPT06	9.5	Silty CLAY	Elliot Formation	271.7	96.1	6.22

5.2.3 Vane Shear Testing

Vane shear testing was carried out by direct-push methods to measure the shear strength of soft soils at locations of CPT01, CPT02 and CPT05. Output of vane shear testing are presented in Appendix F.

Table 5-2: Vane shear test results

Test ID	Depth (m)	Material Type	Origin	Peak Shear Stress (kPa)	Residual Shear Stress (kPa)
CPT01	3.5	Sandy CLAY	Fill	48.7	29.3
	5.0	CLAY	Alluvium	46.5	20.6
	7.0	CLAY	Alluvium	46.4	24.9
	9.0	CLAY	Alluvium	37.4	14.4
	11.0	CLAY	Alluvium	49.7	23.2

Test ID	Depth (m)	Material Type	Origin	Peak Shear Stress (kPa)	Residual Shear Stress (kPa)
	12.0	CLAY	Alluvium	59.4	29.3
CPT02	5.0	Silty CLAY	Alluvium	77.9	39.2
	7.0	CLAY	Alluvium	67.5	27.0
	8.5	CLAY	Alluvium	49.5	26.5
	11.2	CLAY	Alluvium	47.9	21.4
	13.0	CLAY	Alluvium	71.1	32.5
	14.5	CLAY	Alluvium	56.0	21.6
CPT05	4.5	CLAY	Alluvium	44.0	22.5
	6.0	CLAY	Alluvium	41.2	19.2
	7.5	CLAY	Alluvium	47.8	15.5
	10.0	CLAY	Alluvium	73.5	28.6
	11.0	CLAY	Alluvium	50.9	20.1

5.2.4 Falling Head Percolation Testing

Field falling head percolation testing was carried out in four of the levee alignment boreholes i.e. BH01, BH04, BH05 and BH09. Auger drilling was firstly undertaken to a depth of 1.5m - 2.5m below ground surface and then the drilled hole was fully filled with water. Variation of water head level with time was measured by using a dip meter. The test results are used to estimate a field saturated hydraulic permeability of near surface fill or natural materials using an empirical correlation proposed by Reynolds et al (2015). Results of the testing are presented in Figure 5-2.




Figure 5-2: Falling Head Percolation Test Results

5.3 Laboratory Testing

A suite of soil laboratory testing was carried out for soil classification and characteristics of strength and consolidation of soft soils. Aggressivity testing was also conducted to assess the aggressiveness of the soils/water to concrete and steel for durability design. Results of laboratory testing are summarised in the following table.

Laboratory testing certificates will be updated in Appendix G for the next submission.

6 Limitations and Assumptions

6.1 General

The contents of the report are for the sole use of the Department of Housing, Local Government, Planning and Public Works. No responsibility or liability will be accepted to any third party. Data or opinions contained within the report may not be used in other contexts or for any other purposes without prior review and agreement with SMEC.

The recommendations in this report are based on data collected at specific locations using suitable investigation techniques. Only a certain amount of information has been collated to meet the specific financial and technical requirements and this report does not purport to completely describe all the site characteristics and properties. The nature and continuity of the ground between test locations has been inferred using experience and judgement and it must be appreciated that actual conditions could vary from any extrapolated models.

The contractor or client can make their own interpretation of the provided factual data. They should perform any additional tests as necessary for their own purpose. Subsurface conditions, such as groundwater levels, can change over time and this should be borne in mind, particularly if the findings and/or recommendations contained within this report are used after a protracted delay.

It is strongly recommended that any plans and specifications prepared by others and relating to the contents of this report, or any amendments to the original plans and specifications, are reviewed by SMEC to verify that the intent of any recommendations are properly reflected in the design. During construction, we request the opportunity to review our interpretations if the encountered site conditions are significantly different from those inferred in this report. If the report is reproduced, it must be in full. Should there be any queries concerning this report please do not hesitate to contact SMEC.

6.2 Notes Relating to Geotechnical Factual Reports

This geotechnical factual report is prepared by qualified personnel on the information supplied or obtained and are based on current engineering standards of interpretation and assessments.

Information may be gained from limited subsurface testing, surface observations, and previous work, and is supplemented by knowledge of the local geology and experience of the range of properties that may be exhibited by the materials present. For this reason, geotechnical reports should be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely on.

Where the report has been prepared for a specific purpose (e.g. design of a three-storey building), the information and interpretation may not be appropriate if the design is changed (e.g. a twenty-storey building). In such areas, the report and the sufficiency of the existing work should be reviewed by SMEC in the light of the new proposal.

Every care is taken with the report content; however, it is not always possible to anticipate or assume responsibility for the following conditions:

- Unexpected variation in ground conditions. The potential for this depends on the amount of investigative work undertaken.
- Changes in policy or interpretation by statutory authorities.
- The actions of contractors responding to commercial pressures.

If these occur, SMEC would be pleased to resolve the matter through further investigation, analysis or advice.

6.3 Unforeseen Conditions

Should conditions encountered on site differ markedly from those anticipated from the information contained in this report, SMEC should be notified immediately. Early identification of the anomalies generally results in any

problems being more readily resolved and allows re-interpretation and assessment of the implications for future work.

6.4 Subsurface Information

Logs of a borehole, recovered core, test pit, excavated face, or cone penetration tests are an engineering and/or geological interpretation of the subsurface conditions. The reliability of the logged information depends on the drilling/testing method, sampling/observation spacing's and the ground conditions. It is not always possible or economic to obtain continuous high-quality data. It should also be recognised that the volume of material observed or tested is only a fraction of the total subsurface profile.

Interpretation of subsurface information and application to design and construction must take into consideration the spacing of the test locations, the frequency of observations and testing, and the possibility that geological boundaries may vary between observation points.






Groundwater observations and measurements outside of specially designed and constructed piezometers should be treated with care for the following reasons:


- In low permeability soils, groundwater may not seep into an excavation or bore in the short time it is left open.
- A localised perched water table may not represent the true water table.
- Groundwater levels vary according to rainfall events or season.
- Some drilling and testing procedures mask or prevent groundwater inflow.
- The installation of piezometers and long-term monitoring of groundwater levels may be required to adequately identify groundwater conditions.

Appendix A **As built Geotechnical Investigation Plan**



Legends

-  Boreholes (CDM, 2018)
-  Boreholes (Core Consultant, 2019)
-  Boreholes (SMEC, 2024)
-  Cone Penetration Tests (SMEC, 2024)
-  Geophysics Survey (SMEC, 2024)



PAGE SIZE A3

FIGURE TITLE	GI Plan
PROJECT TITLE	Bundaberge East Levee (BEL)
PROJECT NO.	
DRAWING NO.	1
DATE	17-05-2024
CREATED BY	BY
SOURCES	QLD GLOBE



Member of the Surbana Jurong Group

SMEC AUSTRALIA PTY LTD
ABN 47 065 475 149


© SMEC Australia Pty Ltd 2022.
All Rights Reserved

Disclaimer: While all reasonable care has been taken to ensure the information contained on this map is up to date and accurate, this map contains data from a number of sources - no warranty is given that the information contained on this is free from error or omission. Any reliance placed on such information shall be at the sole risk of the user. Please verify the accuracy of all information prior to using it. This map is not a design document.



Legends

- Boreholes (CDM, 2018)
- Boreholes (Core Consultant, 2019)
- Boreholes (SMEC, 2024)
- Cone Penetration Tests (SMEC, 2024)
- Geophysics Survey (SMEC, 2024)



PAGE SIZE A3

FIGURE TITLE	GI Plan
PROJECT TITLE	Bundaberge East Levee (BEL)
PROJECT NO.	
DRAWING NO.	1
DATE	17-05-2024
CREATED BY	BY
SOURCES	QLD GLOBE




SMEC AUSTRALIA PTY LTD
ABN 47 065 475 149

© SMEC Australia Pty Ltd 2022.
All Rights Reserved
Disclaimer: While all reasonable care has been taken to ensure the information contained on this map is up to date and accurate, this map contains data from a number of sources - no warranty is given that the information contained on this is free from error or omission. Any reliance placed on such information shall be at the sole risk of the user. Please verify the accuracy of all information prior to using it. This map is not a design document.



- ### Legends
- Boreholes (CDM, 2018)
 - Boreholes (Core, 2019)
 - Boreholes (SMEC, 2024)
 - Cone Penetration Tests (SMEC, 2024)
 - Geophysics Survey (SMEC, 2024)



PAGE SIZE	A3
FIGURE TITLE	GI Plan
PROJECT TITLE	Bundaberge East Levee (BEL)
PROJECT NO.	
DRAWING NO.	1
DATE	17-05-2024
CREATED BY	BY
SOURCES	QLD GLOBE



SMEC AUSTRALIA PTY LTD
ABN 47 065 475 149


© SMEC Australia Pty Ltd 2022.
All Rights Reserved

Disclaimer: While all reasonable care has been taken to ensure the information contained on this map is up to date and accurate, this map contains data from a number of sources - no warranty is given that the information contained on this is free from error or omission. Any reliance placed on such information shall be at the sole risk of the user. Please verify the accuracy of all information prior to using it. This map is not a design document.



Legends

- Boreholes (CDM, 2018)
- Boreholes (Core Consultant, 2019)
- Boreholes (SMEC, 2024)
- Cone Penetration Tests (SMEC, 2024)
- Geophysics Survey (SMEC, 2024)



PAGE SIZE A3

FIGURE TITLE	GI Plan
PROJECT TITLE	Bundaberge East Levee (BEL)
PROJECT NO.	
DRAWING NO.	1
DATE	17-05-2024
CREATED BY	BY
SOURCES	QLD GLOBE



Member of the Surbana Jurong Group

SMEC AUSTRALIA PTY LTD
ABN 47 065 475 149

© SMEC Australia Pty Ltd 2022.
All Rights Reserved

Disclaimer: While all reasonable care has been taken to ensure the information contained on this map is up to date and accurate, this map contains data from a number of sources - no warranty is given that the information contained on this is free from error or omission. Any reliance placed on such information shall be at the sole risk of the user. Please verify the accuracy of all information prior to using it. This map is not a design document.

Appendix B Explanatory Notes and Borehole Logs

Explanatory Notes of Abbreviations and Terms

Used on Borehole and Excavation Logs

General

Information obtained from site investigations is recorded on log sheets. The “Engineering Log – Borehole or Non Cored Borehole” presents data from drilling operations where a core barrel has not been used to recover material, and information is based on a combination of regular sampling and in-situ testing. The material penetrated in non-core drilling is commonly soil but may include rock. The “Engineering Log – Cored Borehole” presents data from drilling operations where a core barrel has been used to recover material – commonly rock. The “Engineering Log - Excavation” presents data obtained on the subsurface profile from observations of excavations, either natural or man-made. It may contain a scaled, graphical presentation of the typical excavation profile. Refusal of the excavation plant is noted should it occur.

As far as is practicable, the data contained on the log sheets is factual. Some interpretation is inevitable in the assessment of material boundaries in areas of partial sampling, the location of areas of core loss, description and classification of material, estimation of strength and identification of drilling induced fractures. Material description and classification is generally based on AS1726-2017.

Drilling Method

Code	Description
ADT	Auger drilling with TC-bit
ADV	Auger drilling V-bit
AS	Auger screwing
AT	Air track
CA	Casing advancer
CC	Concrete core
CTR	Cable tool rig
DB	Wash bore drag bit
HA	Hand auger
HAND	Hand methods
HF	Hollow flight auger
HMLC	Diamond core 62mm diameter
HQ	Wire line core barrel 64mm diameter
HQ3	Wire line core barrel 62mm diameter
NDD	Non destructive drilling
NMLC	Diamond core 52mm diameter
NQ	Wire line core barrel 47mm diameter
NQ3	Wire line core barrel 45mm diameter
PT	Continuous push tube
PQ	Wire line core barrel 85mm diameter
RAB	Rotary air blast
RC	Reverse circulation
RD	Rotary blade or drag bit
RR	Rock roller
RT	Rotary tricone bit
SD	Sonic drilling
TBX	Tube-X
VC	Vibro-core drilling
WB	Wash bore drilling

Drilling Penetration

Ease of penetration in non-core drilling

VE	Very easy
E	Easy
F	Firm
H	Hard
VH	Very hard

Support and Casing

Code	Description	Code	Description
C	Casing	Hw	114.3 mm
M	Mud	NW	88.9 mm
W	Water	PVC	150 mm

Core Run

Core lifts are identified by a line and depth with core loss per run as a percentage. Core loss is shown in the core run unless otherwise indicated.

Defect Spacing

The average distance between defects is measured parallel to the core axis in mm and may be expressed as a range or average.

Angle / Orientation

Angle from horizontal and orientation to magnetic north.

For inclined cored boreholes the Alpha and Beta angles are presented for orientated core. Alpha (α) is measured relative to the core axis, whilst Beta (β) is measured clockwise from the reference line looking down the core axis in the direction of drilling.

Excavation Method

N	Natural exposure
X	Existing excavation
BB	Tractor mounted backhoe bucket
EX	Hydraulic excavator
EH	Hydraulic excavator with hammer
B	Bulldozer blade
R	Ripper

Water / Drilling Fluid

The drilling fluid used is identified and loss of return to the surface is estimated as a percentage, generally of each core lift.

Symbol	Description
	Water inflow
	Water outflow
	Water level: during drilling or immediately after completion of drilling
	Groundwater level with date observed prior to introduction of fluids or after standpipe construction
Not observed	The observation of groundwater, whether present or not, was not possible due to drilling water, surface seepage or cave in of the borehole / test pit.
Not encountered	The borehole / test pit was dry soon after excavation, however groundwater could be present in less permeable strata. Inflow may have been observed had the borehole / test pit been left open for a longer period.

Colour

The colour of a soil or rock is described in a moist/wet condition using simple terms, such as black, white, grey, red, brown, orange, yellow green or blue. These are modified as necessary by 'pale', 'dark' or 'mottled'. Borderline colours are described as a combination of these colours (e.g. orange-brown). Where a soil or rock consists of a primary colour with a secondary mottling it is described as (primary colour) mottled (first colour) and (secondary colour).

Black						
White						
Grey						
Brown						
Red						
Orange						
Yellow						
Green						
Blue						
< Darker			Paler >			

Description of Soil

- i. Soil name (BLOCK LETTERS)
- ii. Plasticity or particle size of soil
- iii. Colour
- iv. Secondary soil components names & estimated proportions, including their plasticity / particle characteristics, colour
- v. Minor soil components name, estimated proportions, including their plasticity / particle characteristics, colour
- vi. Other minor soil components
- vii. Moisture condition
- viii. Consistency / density
- ix. Structure of soil, geological origin
- x. Additional observations

Particle Size

Term	Grain Size	
Clay	< 2 μ m	
Silt	2 – 75 μ m	
Sand	Fine	0.075 – 0.21 mm
	Medium	0.21 – 0.6 mm
	Coarse	0.6 – 2.36 mm
Gravel	Fine	2.36 – 6.7 mm
	Medium	6.7 – 19 mm
	Coarse	19 – 63 mm
Cobbles	63 – 200 mm	
Boulders	> 200 mm	

Fine Grained and Coarse Grained Soils

Term	Description
Fine Grained Soil (cohesive)	More than 35% of the material less than 63 mm is smaller than 0.075 mm (silts and clays)
Coarse Grained Soil	More than 65% of the material less than 63 mm is larger than 0.075 mm (sands, gravels and cobbles)


Descriptive Terms for Secondary and Minor Components

Designation of Components	In coarse grained soils				In fine grained soils	
	% Fines	Terminology	% Accessory coarse fraction	Terminology	% Sand / Gravel	Terminology
Minor	≤5	trace	≤15	trace	≤15	trace
	>5, ≤12	with	>15, ≤30	with	>15, ≤30	with
Secondary	>12	prefix	>30	prefix	>30	prefix

Plasticity – Fine Grained Soils

Liquid Limit (LL) %	Description
≤ 35	Low plasticity (L)
>35 to ≤ 50	Medium plasticity (I)
> 50	High plasticity (H)

Plasticity Chart– Fine Grained Soils



Consistency Terms – Fine Grained Soils

Term	Undrained shear strength (kPa)	Indicative SPT (N) Blow Count	Field Guide to Consistency
Very Soft (VS)	<12	0 – 2	Easily penetrated several centimetres by fist, exudes between fingers when squeezed in fist
Soft (S)	12 – 25	2 – 4	Easily penetrated several centimetres by thumb, easily moulded by light finger pressure
Firm (F)	25 – 50	4 – 8	Can be penetrated several centimetres by thumb with moderate effort, and moulded between the fingers by strong pressure
Stiff (St)	50 – 100	8 – 15	Readily indented by thumb but penetrated only with difficulty. Cannot be moulded by fingers
Very Stiff (VSt)	100 – 200	15 – 30	Readily indented by thumb nail, still very tough
Hard (H)	>200	>30	Indented with difficulty by thumb nail, brittle
Friable (Fr)	-		Can be easily crumbled or broken into small pieces





Density Terms – Coarse Grained Soils

Term	Density Index (%)	SPT (N) Blow Count
Very Loose (VL)	< 15	0 – 4
Loose (L)	15 – 35	4 – 10
Medium Dense (MD)	35 – 65	10 – 30
Dense (D)	65 – 85	30 – 50
Very Dense (VD)	> 85	>50

Particle Characteristics – Coarse Grained Soils

Term	Description
Well Graded	Having good representation of all particle sizes
Poorly graded	With one or more intermediate size poorly represented
Gap graded	With one or more intermediate sizes absent
Uniform	Essentially of one size

Angularity – Coarse Grained Soils

	Rounded
	Sub-rounded
	Angular
	Sub-angular

Origin of Soil

Fill	Formed by humans
Aeolian	Formed by wind
Alluvial	Formed by streams and rivers
Colluvial	Formed on slopes (talus)
Estuarine	Formed in marine environments
Lacustrine	Formed in lakes
Residual	Formed by weathering insitu




















Soil Moisture

	Term	Code	Description
Coarse Grained	Dry	D	Looks and feels dry and free running
	Moist	M	Soil feels cool, darkened in colour, soils tend to stick together, soil grains do not run freely through fingers and no visible free water
	Wet	W	Soil feels cool, darkened in colour, soils tend to stick together, free water on remoulding
Fine Grained	Moist, Less than Plastic Limit	W < PL	Hard and friable or powdery, moisture content well below Plastic Limit
	Moist, Near Plastic Limit	W ≈ PL	Soil feels cool, darkened in colour, can be moulded, near Plastic Limit
	Moist, Wet of Plastic Limit	W > PL	Soil feels cool, dark, usually weakened, free water, moisture content well above Plastic Limit
	Wet, Near Liquid Limit	W ≈ LL	Soil exudes easily
	Wet, Wet of Liquid Limit	W > LL	Soil behaves as a liquid

Boundary Classifications

Soils possessing characteristics of two groups are designated by combinations of group symbols. For example, GW-GC, well graded gravel-sand mixture with clay binder.

Graphic Symbols

	Asphalt		MH
	CH		ML
	CI		OH
	CL		OL
	Concrete		PT
	Fill		SC
	GC		SM
	GM		SP
	GP		SW
	GW		

Soil Classification

Soils are described in general accordance with AS1726-2017 as shown below.

FIELD IDENTIFICATION PROCEDURES (Excluding particles larger than 63 mm and basing fractions on estimated mass)				GROUP SYMBOL	PRIMARY NAME	
COARSE GRAINED SOILS More than 65% of the material is less than 63 mm and is larger than 0.075 mm	A particle size of 0.075 is about the smallest size distinguishable to the naked eye	GRAVELS More than half of coarse fraction is larger than 2.36 mm	CLEAN GRAVELS (Little or no fines)	Wide range in grain size and substantial amounts of all intermediate particle sizes, not enough fines to bind coarse grains, no dry strength; ≤ 5% fines	GW	GRAVEL
				Predominantly one size or a range of sizes with more intermediate sizes missing, not enough fines to bind coarse grains, no dry strength; ≤ 5% fines	GP	GRAVEL
			GRAVELS w/ FINES (Appreciable amount of fines)	'Dirty' materials with excess of non-plastic fines, none to medium dry strength; ≥ 12% silty fines	GM	SILTY GRAVEL
			'Dirty' materials with excess of plastic fines, medium to high dry strength; ≥ 12% clayey fines	GC	CLAYEY GRAVEL	
		SANDS More than half of coarse fraction is smaller than 2.36 mm	CLEAN SANDS (Little or no fines)	Wide range in grain size and substantial amounts of all intermediate particle sizes, not enough fines to bind coarse grains, no dry strength; ≤ 5% fines	SW	SAND
				Predominantly one size or a range of sizes with more intermediate sizes missing, not enough fines to bind coarse grains, no dry strength; ≤ 5% fines	SP	SAND
	SANDS w/ FINES (Appreciable amount of fines)		'Dirty' materials with excess of non-plastic fines, none to medium dry strength; ≥ 12% silty fines	SM	SILTY SAND	
		'Dirty' materials with excess of plastic fines, medium to high dry strength; ≥ 12% clayey fines	SC	CLAYEY SAND		
	FINE GRAINED SOILS More than 35% of the material less than 63 mm is less than 0.075 mm	IDENTIFICATION PROCEDURES ON FRACTIONS < 0.075 mm				
		SILTS AND CLAYS Liquid Limit < 50%	DRY STRENGTH	DILATANCY	TOUGHNESS	GROUP SYMBOL
None to low			Slow to rapid	Low	ML	SILT
Medium to high			≥ 12% clayey fines	Medium	CL, CI	CLAY
SILTS AND CLAYS Liquid Limit > 50%		Low to medium	Slow	Low	OL	ORGANIC SILT
		Low to medium	None to slow	Low to medium	MH	SILT
		High to very high	None	High	CH	CLAY
		Medium to high	None to very slow	Low to medium	OH	ORGANIC CLAY
HIGHLY ORGANIC SOILS: readily identified by colour, odour, spongy feel and frequently fibrous texture				PT	PEAT	

Description of Rock

- i. Rock name (BLOCK LETTERS)
- ii. Grain size and mineralogy
- iii. Colour
- iv. Fabric and texture
- v. Features, inclusions, minor components, moisture content and durability
- vi. Strength
- vii. Weathering and/or alteration
- viii. Rock mass properties – discontinuities and structure of rock
- ix. Interpreted stratigraphic unit
- x. Additional observations including geological structure

Simple rock names are used to provide a reasonable engineering description, rather than a precise geological classification. The rock name is chosen by considering the nature and shape of the grains or crystals, the texture and fabric of the rock material, the geological structure and setting, and information from the geological map of the area. Further guidance on the naming of rocks can be found in AS1726-2017, Tables 15, 16, 17 and 18. Typical rock types are described below, though subject to site specific variations.

Rock Type	Description	Example of Rock Name
Sedimentary	Formed by deposited beds of sediments, have grains that are cemented together and often rounded. Significant porosity	<p>COMMON: Conglomerate, Breccia, Sandstone, Mudstone, Siltstone, Claystone</p> <p>≥90% CARBONATE: Limestone, Dolomite, Calcirudite, Calcarenite, Calcisiltite, Calcilutite</p> <p>PYROCLASTIC: Agglomerate, Volcanic Breccia, Tuff</p>
Igneous	Formed from molten rock and have a crystalline texture. Typically massive and low porosity. Rock types are from coarse to fine grained.	<p>HIGH QUARTZ CONTENT: Granite, Microgranite, Rhyolite</p> <p>MODERATE QUARTZ CONTENT: Diorite, Microdiorite, Andesite</p> <p>LOW QUARTZ CONTENT: Gabbro, Dolerite, Basalt</p>
Metamorphic	Formed when rocks are subject to heat and/or pressure and have typically have directional fabric. Typically have low porosity and crystalline structure. Rock types are from coarse to fine grained	<p>FOLIATED: Gneiss, Schist, Phyllite, Slate</p> <p>NON-FOLIATED: Marble, Quartzite, Serpentinite, Hornfels</p>
Duricrust	Formed as part of a weathering profile and show evidence of being cemented in situ. Cementation is typically irregular and exhibits replacement textures.	<p>Ferricrete (Iron oxides and hydroxides)</p> <p>Silicrete (Silica)</p> <p>Calcrete (Calcium carbonate)</p> <p>Gypcrete (Gypsum)</p>

Note: () denotes dominant cementing mineralogy

Grain Size

Terms describing dominate grain size in sedimentary rocks.

Term	Grain size
Coarse	Mainly 0.6 mm to 2 mm
Medium	Mainly 0.2 mm to 0.6 mm
Fine	Mainly 0.06mm (just visible) to 0.2 mm

Terms describing dominate grain size in igneous and metamorphic rocks

Term	Grain size
Coarse	Mainly greater than 2 mm
Medium	0.06 mm to 2 mm
Fine	Mainly less than 0.06 mm (just visible) to 0.2mm

Texture and Fabric

Sedimentary rocks

Thickness	Bedding Term
< 6 mm	Thinly laminated
6 – 20 mm	Laminated
20 – 60 mm	Very thinly bedded
60 – 200 mm	Thinly bedded
0.2 – 0.6 m	Medium bedding
0.6 – 2 m	Thickly bedded
> 2 m	Very thickly bedded

Igneous rocks

Term	Definition
Amorphous	Indicates that the rock has no obvious crystalline structure
Crystalline	A regular molecular structure, showing crystal structure and symmetry.
Cryptocrystalline	The texture comprises crystals that are too small to recognise under an ordinary microscope. Indistinctly crystalline.
Porphyritic	Indicates the presence of phenocrysts (relatively large crystals in a fine grained ground mass) in igneous rocks.
Flow banded	Indicates visible flow lines in volcanic rocks and some intrusive rocks
Glassy	Entirely glass like. No crystalline units and without crystalline structure.
Vesicular	A texture of volcanic rocks that indicates the presence of vesicles (small gas bubbles). Where the vesicles are filled with a mineral substance they are termed Amygdales and the texture is Amygdaloidal.

Metamorphic

Term	Definition
Foliation	The parallel arrangement of minerals due to metamorphic process, which shall be defined by the terms in weak, moderate and strongly foliated.
Porphyroblastic	A texture indicating the presence of porphyroblasts (larger crystals formed by recrystallization during metamorphism, such as garnet or staurolite in a mica schist).
Cleavage	A type of foliation developed in fine grained metamorphic rocks such as slates.

Bedding and Fabric Development

Type	Definition
Massive	No obvious development of bedding – rock appears homogeneous
Poorly Developed	Bedding is barely obvious as faint mineralogical layering or grain size banding, but bedding planes are poorly defined.
Well Developed	Bedding is apparent in outcrops or drill core as distinct layers or lines marked by mineralogical or grain size layering.
Very Well Developed	Bedding is often marked by a distinct colour banding as well as by mineralogical or grain size layering.
Indistinct fabric	There is little effect on strength properties
Distinct Fabric	The rock may break more easily parallel to the fabric

Rock Strength

Term (Code)	UCS (MPa)	Is ₍₅₀₎ (MPa)	Field Guide to Strength
Very Low (VL)	0.6 – 2	> 0.03 to ≤0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with knife; too hard to cut a triaxial sample by hand. Pieces up to 3 cm thick can be broken by finger pressure.
Low (L)	2 - 6	> 0.1 to ≤ 0.3	Easily scored with a knife; indentations 1 mm to 3 mm show in the specimen with firm blow of the pick point; has dull sound under hammer. A piece of core 150 mm long 50 mm in diameter may be broken by hand. Sharp edges of core may be friable and break during handling.
Medium (M)	6 - 20	> 0.3 to ≤ 1.0	Readily scored with a knife; a piece of core 150 mm long by 50 mm in diameter can be broken by hand with difficulty.
High (H)	20 - 60	> 1 to ≤ 3	A piece of core 150 mm long by 50 mm in diameter cannot be broken by hand but can be broken by a pick with a single firm blow; rock rings under hammer.
Very High (VH)	60 -200	> 3 to ≤ 10	Hand specimen breaks with pick after more than one blow; rock rings under hammer.
Extremely High (EH)	>200	> 10	Specimen requires many blows with geological pick to break through intact material; rock rings under hammer.

Rock strength is assessed by laboratory Uniaxial Compressive Strength (UCS) testing and/or Point Load Strength Index (PLT) testing to obtain the Is₍₅₀₎ the strength table implies a 20 times correlation between Is₍₅₀₎ and UCS used for classification. Note however, multiplier may range from 4 (e.g. some carbonated and low strength rocks) to 40 (e.g. some igneous rocks and/or some high strength rocks). A site specific correlation based on testing, previous investigation or literature may be used where available. These terms refer to the strength of the rock material and not to the strength of the rock mass which may be considered weaker due to the effect of rock defects.

Visual Log

A diagrammatic plot of defects showing type, spacing and orientation in relation to the core axis.

—————	Defects open in situ or clay sealed
-----	Defects closed in-situ
.....	Drill induced fractures or handling breaks
■	Infilled seam

Rock Weathering and or Alteration Classification

Term (Code)	Definition		
Residual soil (RS)	Soil developed on extremely weathered rock. The rock mass structure and substance fabric are no longer evident but the soil has not been significantly transported.		
Extremely weathered (EW) Extremely altered (XA)	Rock is weathered to such an extent that it has 'soil' properties, i.e. it either disintegrates or can be remoulded in water, but the texture of original rock is still evident.		
Highly weathered (HW) Highly Altered (HA)	Distinctly weathered (DW)* Distinctly Altered (DA)	Whole rock material is discoloured usually by extent that iron staining or bleaching and other signs of chemical or physical decomposition are evident. Porosity and strength may be increased or decreased compared to the fresh rock usually as a result of iron leaching or deposition. The colour and strength of the original rock substance is no longer recognisable	*Where is it not practical to distinguish between 'HW' and 'MW'. Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores
Moderately weathered (MW) Moderately Altered (MA)			
Slightly weathered (SW) Slightly altered (SA)	Rock is slightly discoloured but shows little or no change of strength from fresh rock		
Fresh rock (F)	Rock shows no sign of decomposition or staining.		

Rock Core Recovery

TCR = Total Core Recovery (%)

$$\frac{\text{Length of Core Recovered}}{\text{Length of Core run}} \times 100$$

SCR = Solid Core Recovery (%)

$$\frac{\text{Sum Length of Cylindrical Core Recovered}}{\text{Length of Core run}} \times 100$$

RQD = Rock Quality Designation (%)

$$\frac{\text{Sum Length of Sound Core Pieces > 100mm in length}}{\text{Length of Core run}} \times 100$$

Types of Discontinuities

Term	Code	Description
Parting	Pt	A defect parallel or sub-parallel to a layered arrangement of mineral grains or micro-fractures, which has caused planar anisotropy in the rock substance.
Joint	Jt	A defect across which the rock substance has little tensile strength, but that is not related to textural or depositional features within the rock substance.
Sheared Zone	SZ	A zone with roughly parallel planar boundaries of rock substance consisting of closely spaced joints with smooth slickensided surfaces often curved. The joints divide the rock mass into unit blocks usually of lenticular or wedge shape.
Crushed Zone	CZ	A zone or seam with roughly parallel planar boundaries of rock substance composed of disoriented, usually angular, fragments of the host rock substance
Seam	Se	A zone or seam with roughly parallel boundaries, infilled by soil (IS) or decomposed rock (DS)
Fault	F	A fracture (defect) in rock along which there has been an observable amount of displacement.
Vein	Ve	A zone of minerals intruded into a joint or fissures.

Type of Structures

Term	Code	Description
Bedding	Bg	A layered arrangement of minerals parallel to the surface of deposition which has caused planar anisotropy in the rock substance.
Cleavage	C	An alignment of fine grained minerals caused by deformation.
Schistosity	SH	A layered arrangement of minerals to each other
Foliation	Fo	A planar alignment of minerals caused by deformation.
Void	Vo	A completely empty space
Dyke	DK	Sheet-like bodies of igneous rock that cut across sedimentary bedding or foliations in rocks. They may be single or multiple in nature
Sill	Sl	A sill is an intrusion of magma that spreads underground between the layers of another kind of rock
Contact	Cn	A contact between intrusive and stratigraphic units.
Boundary	Bd	A distinct boundary between two stratigraphic units

Note: Drill breaks (DB) and handling breaks (HB) are not included as natural discontinuity.

Discontinuity Spacing

Spacing (mm)	Description
>6000	Extremely Widely Spaced
2000 - 6000	Very Widely Spaced
600 - 2000	Widely Spaced
200 - 600	Medium Spaced
60 - 200	Closely Spaced
20 - 60	Very Closely Spaced
<20	Extremely Closely Spaced

Discontinuity Planarity

Code	Description
Cu	Curved – A defect with a gradual change in orientation
Ir	Irregular – A defect with many sharp changes in orientation
Pl	Planar – Defect forms a continuous plane without variation in orientation
St	Stepped – A defect with distinct sharp steps or step
Un	Undulose – A defect with undulations
Vu	Vuggy – An open void with crystallisation
Wv	Wavy – A wavy defect surface

Discontinuity Roughness

Abbreviation	Description
Ro	Rough – Many small surface irregularities generally related to the grain size of the parent rock
Sm	Smooth – Few or no surface irregularities related to the grain size of the parent rock
Po	Polished – Planes have a distinct sheen or a smoothness
Sl	Slickensided – Planes have a polished, grooved or striated surface consistent with differential movement of the parent rocks along the plane
VR	Very rough – many large surface irregularities, amplitude generally more than 1mm

Infill Material

Code	Name	Code	Name
Ca	Calcite	Gp	Gypsum
Ch	Chlorite	Mn	Manganese
Cl	Clay	MS	Secondary mineral
Co	Coal	Py	Pyrite
Fe	Limonite / Ironstone	Um	Unidentified mineral
Fe Cl	Iron oxide clay	Qz	Quartz
Fl	Feldspar	X	Carbonaceous

Discontinuity Observation

Term	Code	Description
Clean	CN	No visible coating or infill
Stain	SN	No visible coating or infill but surfaces are discoloured by mineral staining
Veneer <1 mm	VNR	A visible coating or soil or mineral substance but usually unable to be measured. If discontinuous over the plane, patchy veneer.
Coating >1 mm to <10 mm	CT	A visible coating or infilling of soil or mineral substance. Describe composition and thickness.
Filling (Filled) >10 mm	FLD	A visible filling of soil or mineral substance. Describe composition and thickness.

Samples and Field Tests

Code	Description
B	Bulk disturbed sample
BLK	Block sample
C	Core sample
DS	Small disturbed sample
ES	Soil sample for environmental testing
EW	Water sample for environmental testing
FP	Pressuremeter
G	Gas sample
H	Hydraulic fracturing
HP	Hand penetrometer test
I	Impression device
IS ₍₆₀₎	Point Load Index
K	Permeability
LB	Large bulk disturbed sample
N	Standard penetration test result (N* denotes SPT sample recovery)
O	Core orientation
P	Piston sample
PID	Photoionisation detector reading in ppm
R	Hammer bouncing / refusal
SPT	Standard Penetration Test
U	Undisturbed push in sample
UCS	Uniaxial Compressive Strength
U50	Undisturbed tube sample (50 mm diameter)
U75	Undisturbed tube sample (75 mm diameter)
VS	Vane shear test
● (A)	Axial Test
○ (D)	Diametral Test
□	Irregular Lump test











Completion Details

Type	Description
Collapse	Exploratory hole collapsed before reaching planned depth
Equipment Failure	Boring or excavator equipment operational failure
Flooding	Flooding of excavation
Machine Limit	Limit of machine capability reached
Obstruction	Obstruction preventing further advancement
Possible services	Indication of possible services below
Services present	Services encountered during exploratory hole
Squeezing	Hole squeezing boring equipment
Target Depth	Depth reached as planned
Target Depth Instrumentation Installed	Depth reached as planned instrumentation installed
Target Depth Standpipe Installed	Depth reached as planned open standpipe constructed
Material Refusal	Material preventing further advancement

Laboratory Tests

Code	Description
ACM	Asbestos Containing Material
CD	Consolidated Drained
CU	Consolidated Undrained
LL	Liquid Limit
LS	Linear Shrinkage
MC	Moisture Content
MDD	Maximum Dry Density
OMC	Optimum Moisture Content
PBT	Plate Bearing Test
PI	Plasticity Index
PL	Plastic Limit
PSD	Particle Size Distribution
ρ_b	Bulk Density
ρ_p	Particle Density
ρ_d	Dry Density
UU	Undrained Unconsolidated

Backfill / Standpipe Detail

Symbol	Description	Symbol	Description
	Cement seal		Filter pack: sand filter
	Grout backfill		Filter pack: gravel filter
	Blank pipe		Bentonite seal
	Slotted pipe		Cutting - excavated material backfill
	Surface Completion: Monument Above Ground		Surface Completion: Gatic Ground Monument

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435335.7 m
 North 7250162.0 m
 Elevation 4.28 m
 Datum MGA2020-56/AHD

Start Date 21/4/2024
 End Date 21/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey North



Member of the Surlana Jurong Group
 Borehole Identifier: **BH01**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation	
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) P/R uncorrected PID (ppm)														
					0.50m SPT 3,6,7 N=13 (0.45m REC) 0.95m		0.60m PP=320kPa 0.70m PP=300kPa		4.28 4.3				FILL Sandy CLAY: medium to high plasticity, brown to dark brown, sand is fine to medium grained; trace rootlets.	w<PL					FILL		
					1.50m SPT 1,2,4 N=6 (0.45m REC) 1.95m		1.80m PP=150kPa 1.90m PP=150kPa		1.20 3.3				Sandy CLAY: high plasticity, dark brown and grey, sand is fine to medium grained; trace fine grained gravel; trace rootlets.	w=PL	St				ALLUVIAL SOIL		
					2.50m SPT 2,2,7 N=9 (0.45m REC) 2.95m		2.70m PP=150kPa 2.80m PP=150kPa		2.0 2.3	CH			2.30: Becoming brown, dark brown and black								
					3.50m SPT 2,3,7 N=10 (0.45m REC) 3.95m		3.70m PP=230kPa 3.80m PP=230kPa		3.0 1.3	CH			3.20 1.08	CLAY: high plasticity, orange-brown and grey, trace fine grained sand.	w<PL						
					4.50m SPT HW/450mm (0.45m REC)		4.50m VS=43kPa 4.70m PP=80kPa 4.80m PP=80kPa		4.0 0.3				4.50 -0.22	CLAY: low to medium plasticity, dark grey to grey.		F				MARINE SOIL	
					5.50m SPT HW/450mm (0.45m REC)		5.70m PP=60kPa 6.00m VS=41kPa		5.0 -0.7												
							7.50m VS=47kPa		6.0 -1.7	CL -CL											
									7.0 -2.7												
									8.0												

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 21/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 1 of 3

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435335.7 m
 North 7250162.0 m
 Elevation 4.28 m
 Datum MGA2020-56/AHD

Start Date 21/4/2024
 End Date 21/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey North



Member of the Surbana Jurong Group
 Borehole Identifier: BH01

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
								8.0 -3.7				CLAY: low to medium plasticity, dark grey to grey. (continued)	w<PL	St				MARINE SOIL	
					8.50m SPT HW/450mm (0.45m REC)			8.70m PP=110kPa 8.80m PP=110kPa		CL -Cl									9.0
					10.00m SPT HW/450mm (0.45m REC)			10.00m VS=73kPa 10.30m PP=110kPa 10.40m PP=100kPa											10.0
								11.00m VS=51kPa											11.0
					11.50m SPT HW/450mm (0.45m REC)			11.60m PP=40kPa 11.70m PP=60kPa		CL -Cl	11.20 -6.92	Sandy CLAY: low to medium plasticity, dark grey to dark brown, sand is fine to coarse grained.		S to F					12.0
											12.50 -8.22	CLAY: low to medium plasticity, dark grey, with fine to coarse grained sand.							13.0
					13.00m SPT 5,7,2 N=9 (0.45m REC) 13.45m					CL -Cl	13.20 -8.92	Gravelly SAND: fine to medium grained, grey to pale grey, gravel is fine to medium grained, sub-angular to sub-rounded; trace low plasticity clay.	W	L				ELLIOT FORMATION	14.0
										SP									15.0
					14.50m SPT 3,5,5 N=10 (0.45m REC) 14.95m						14.50 -10.22	Clayey SAND: fine to coarse grained, dark grey, clay is low plasticity; with fine to medium grained, sub-angular to sub-rounded gravel.							15.0
										SC								15.51: Losing water	16.0

Observations and Comments

Notes

Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 21/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 2 of 3

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435018.3 m
 North 7250106.6 m
 Elevation 5.03 m
 Datum MGA2020-56/AHD

Start Date 28/4/2024
 End Date 28/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH02**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
								8.0 -3.0				CLAY: low to medium plasticity, dark grey to grey, trace fine to medium grained sand. (continued)	w>PL	F				MARINE SOIL	
					9.00m SPT HW/450mm (0.45m REC)			9.0 -4.0				9.00: Trace fine to medium grained, sub-rounded gravel							
					10.50m SPT HW/450mm (0.45m REC)			10.0 -5.0											
								10.70m PP=70kPa											
								11.00m VS=50kPa											
					12.00m SPT HW/450mm (0.45m REC)			11.0 -6.0											
								12.00m VS=59kPa											
								12.30m PP=70kPa											
								12.35m PP=70kPa											
								Not Observed											
					13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m			12.0 -7.0											
								12.30m PP=70kPa											
								12.35m PP=70kPa											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											
								13.50m SPT 2.4, 4 N=8 (0.45m REC) 13.95m											

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435018.3 m
 North 7250106.6 m
 Elevation 5.03 m
 Datum MGA2020-56/AHD

Start Date 28/4/2024
 End Date 28/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: BH02

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP												
				SPTLS	SPT 3070mm N=R (0.07m REC)			24.0 -19.0			Sandy CLAY; medium to high plasticity, pale grey, sand is fine to medium grained; (Extremely Weathered). CLAY: high plasticity, pale grey, trace fine grained sand.	w<PL	VSt - H				EXTREMELY WEATHERED MATERIAL RESIDUAL SOIL	
								25.0 -20.0										
				SPTLS	SPT 10,19,25 N=44 (0.45m REC) 25.95m			25.50m										
								26.0 -21.0										
				SPTLS	SPT 8,12,18 N=30 (0.45m REC) 27.45m			27.00m		CH								
								27.0 -22.0										
				SPTLS	SPT 9,15,21 N=36 (0.45m REC) 28.95m			27.30m PP>500kPa 27.40m PP>500kPa										
								28.0 -23.0										
				SPTLS	SPT 6,8,11 N=19 (0.45m REC) 30.45m			28.50m										
								28.60m PP=420kPa 28.70m PP=480kPa										
								29.0 -24.0										
								30.0 -25.0										
								30.45										
								31.0 -26.0			Hole Terminated at 30.45 m Target Depth							
								32.0										

Draft

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 28/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page4 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435577.6 m
 North 7250229.6 m
 Elevation 3.79 m
 Datum MGA2020-56/AHD

Start Date 30/4/2024
 End Date 30/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier:

BH03

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation	
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)														
					0.50m		0.20m PP>500kPa 0.40m PP>500kPa		3.79				TOPSOIL Sandy CLAY: medium to high plasticity, dark brown to brown, sand is fine to medium grained; trace fine to coarse grained, sub-angular to sub-rounded gravel; trace rootlets.	w<PL					TOPSOIL		
					SPT 5,7,7 N=14 (0.45m REC) 0.95m				3.29				FILL Sandy CLAY: medium to high plasticity, dark brown, sand is fine to medium grained.						FILL		
					1.50m		1.60m PP=300kPa 1.70m PP=200kPa		1.70				CLAY: high plasticity, red-brown and grey, with fine to medium grained sand.		F				ALLUVIAL SOIL		
					SPT 1,3,3 N=6 (0.45m REC) 1.95m				2.09	CH											
					2.50m				2.50				Sandy CLAY: medium to high plasticity, red-brown and grey, sand is fine to medium grained.		VSt - H						
					SPT 9,13,16 N=29 (0.45m REC) 2.95m				1.29	CI -CH											
					4.00m				3.20				Gravelly SAND: fine to coarse grained, grey and red-brown, gravel is fine to coarse grained, sub-angular to sub-rounded; with low plasticity clay.	M	D						
					SPT 30 HB N=R (0.15m REC) 4.15m				0.59	SP											
					Not Observed				4.00				Sandy CLAY: medium to high plasticity, pink-grey, sand is fine to medium grained; (Extremely Weathered mudstone).						EXTREMELY WEATHERED MATERIAL		
					7.00m		7.30m PP=300kPa 7.40m PP=340kPa		-0.21												
					SPT 9,14,10 N=24 (0.45m REC) 7.45m				7.00	CI -CH			Sandy CLAY: medium to high plasticity, grey mottled white, sand is fine to coarse grained; trace fine to medium grained, sub-angular to sub-rounded gravel.	w=PL	VSt				ALLUVIAL SOIL		
									-3.27												
									7.40				CLAY: high plasticity, grey to pale grey, trace fine grained sand.								
									-3.61	CH											

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 30/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 1 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435577.6 m
 North 7250229.6 m
 Elevation 3.79 m
 Datum MGA2020-56/AHD

Start Date 30/4/2024
 End Date 30/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: BH03

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
					SPT 5.6, 6 N=12 (0.45m REC) 16.45m			16.0 -12.2				Sandy CLAY: medium plasticity, brown to pale brown, sand is fine to coarse grained; trace fine to coarse grained, sub-rounded gravel. (continued)	w>PL	St				ELLIOT FORMATION	
								17.0 -13.2	Cl										
					17.50m SPT 9, 13, 12 N=25 (0.45m REC) 17.95m			17.50 -13.77				Sandy CLAY: medium to high plasticity, pale brown, white, grey and brown, sand is fine to coarse grained; with fine to coarse grained, sub-angular to sub-rounded gravel.	w=PL						
								18.0 -14.2											
					19.00m SPT 4, 6, 17 N=23 (0.45m REC) 19.45m			19.0 -15.2											
								19.30m PP=110kPa 19.40m PP=150kPa	-Cl -CH										
					20.50m SPT 5, 7, 11 N=18 (0.45m REC) 20.95m			20.0 -16.2											
								20.70m PP=240kPa 20.80m PP=260kPa											
					22.00m SPT 7, 12, 18 N=30 (0.45m REC) 22.45m			21.0 -17.2											
								22.0 -18.2				CLAY: high plasticity, grey to pale grey, trace fine grained sand.		H					RESIDUAL SOIL 22.00: Not enough sample to take pocket penetrometer test
					23.50m SPT 5, 10, 14 N=24 (0.45m REC) 23.95m			22.0 -18.27	CH										
								23.0 -19.2											
								23.70m PP=420kPa 23.80m											
								24.0 -19.2											

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 30/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 3 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435577.6 m
 North 7250229.6 m
 Elevation 3.79 m
 Datum MGA2020-56/AHD

Start Date 30/4/2024
 End Date 30/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH03**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)													
							PP=430kPa	Net Observed	24.0 -20.2				CLAY: high plasticity, grey to pale grey, trace fine grained sand. (continued)	w=PL	H				RESIDUAL SOIL	
					25.00m				25.0 -21.2		CH	25.45	Hole Terminated at 25.45 m Target Depth							
					SPT 6.11, 11 N=22 (0.45m REC) 25.45m		25.30m PP=420kPa 25.40m PP=400kPa													
									26.0 -22.2											
									27.0 -23.2											
									28.0 -24.2											
									29.0 -25.2											
									30.0 -26.2											
									31.0 -27.2											
									32.0 -28.2											

Draft

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 30/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 4 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435090.0 m
 North 7250122.8 m
 Elevation 7.25 m
 Datum MGA2020-56/AHD

Start Date 19/4/2024
 End Date 21/4/2021

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH04**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP												
				U90				8.0 -0.8			CLAY: medium to high plasticity, dark grey to grey, trace fine grained sand. (continued)	w=PL	S - F				MARINE SOIL	
								9.0 -1.8										
					10.00m SPT HW/450mm (0.45m REC)			10.00 -2.8	CI		10.00: Trace fine to medium grained sand							
								11.0 -3.8										
					11.50m SPT HW/450mm (0.45m REC)			11.50 -4.25			CLAY: low to medium plasticity, dark grey to grey.	w=PL	S					
								12.0 -4.8										
					13.00m SPT HW/450mm (0.45m REC)			13.0 -5.8										
								14.0 -6.8	CL - CI									
				U90				15.0 -7.8										
								16.0 -8.8										

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 21/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 2 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435090.0 m
 North 7250122.8 m
 Elevation 7.25 m
 Datum MGA2020-56/AHD

Start Date 19/4/2024
 End Date 21/4/2021

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier:

BH04

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation	
					SPT (Recovered length)	DCP														PP (kPa) VS (kPa) P/R uncorrected PID (ppm)
								16.0			16.20	CLAY: low to medium plasticity, dark grey to grey. (continued)	w>PL	S				MARINE SOIL		
								-8.8	Cl		-9.05	CLAY: medium plasticity, black to dark grey. Sandy CLAY: medium plasticity, black to dark grey, sand is fine to coarse grained. CLAY: medium plasticity, black to dark grey.							16.5	
								17.0	Cl		17.70									17.0
								-9.8			-10.45	Clayey SAND: fine to coarse grained, grey to pale grey, clay is low plasticity; with fine grained, sub-angular to rounded gravel.	W	L				ELLIOT FORMATION	18.0	
								18.0			-12.05									19.0
								-10.8	SC		19.30	CLAY: medium to high plasticity, pale grey to pale red-brown.	w=PL	VSt				RESIDUAL SOIL	19.5	
								19.0			-12.8									20.0
								-11.8			20.50									20.5
								20.0			20.90									21.0
								-12.8			22.00									22.0
								21.0			22.45									22.5
								-13.8			23.00									23.0
								22.0			23.50									23.5
								-14.8			-16.35	Gravelly SAND: fine to coarse grained, grey to pale grey, gravel is fine to medium grained, sub-angular to sub-rounded; trace low plasticity clay. CLAY: high plasticity, pale grey and mottled red-brown, (Extremely Weathered).	W	VD				EXTREMELY WEATHERED MATERIAL	24.0	
								23.0												24.0
								-15.8												
								23.50												
								-16.35												
								24.0												

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 21/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 3 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435090.0 m
 North 7250122.8 m
 Elevation 7.25 m
 Datum MGA2020-56/AHD

Start Date 19/4/2024
 End Date 21/4/2021

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier:

BH04

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)													
								Net Observed	24.0 -16.8				CLAY: high plasticity, pale grey and mottled red-brown, (Extremely Weathered). (continued)						EXTREMELY WEATHERED MATERIAL	
					25.00m SPT 30/100mm HB N=R (0.10m REC) 25.10m				25.0 -17.8		25.10		Hole Terminated at 25.10 m Refusal							
									26.0 -18.8											
									27.0 -19.8											
									28.0 -20.8											
									29.0 -21.8											
									30.0 -22.8											
									31.0 -23.8											
									32.0											

Draft

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 21/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 4 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435062.0 m
 North 7250140.0 m
 Elevation 6.66 m
 Datum MGA2020-56/AHD

Start Date 17/4/2024
 End Date 18/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH05**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
				U90				8.0 -1.3				CLAY: medium to high plasticity, dark grey, trace fine grained sand. (continued)	w>PL	S				MARINE SOIL	
								9.0 -2.3		CI-CH									
					10.00m SPT HW/450mm (0.45m REC)			10.0 -3.3		CI-CH	10.20 -3.64	Sandy CLAY: medium to high plasticity, dark grey, sand is fine to coarse grained. CLAY: medium to high plasticity, dark grey.							
								11.0 -4.3		CI-CH									
					11.50m SPT HW/450mm (0.45m REC)			11.0 -4.3		CI-CH									
								12.0 -5.3											
					13.00m SPT HW/300mm,1 N=1 (0.45m REC) 13.45m			13.0 -6.3		CI-CH	13.00 -6.34	CLAY: medium to high plasticity, dark brown and dark grey, trace fine grained sand.	w=PL						
								14.0 -7.3											
				U90				15.0 -8.3		CI-CH									
								16.0											

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 18/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 2 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435062.0 m
 North 7250140.0 m
 Elevation 6.66 m
 Datum MGA2020-56/AHD

Start Date 17/4/2024
 End Date 18/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH05**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
					SPT HW/450mm (0.45m REC)			16.0			16.20	CLAY: medium to high plasticity, dark brown and dark grey, trace fine grained sand. (continued)	w=PL	S				MARINE SOIL	
						16.20m PP=100kPa 16.45m PP=110kPa		-9.3	CI-CH		-9.54	CLAY: medium to high plasticity, dark grey and grey, with fine to medium grained sand.							
					17.50m SPT 10,10,8 N=18 (0.45m REC) 17.95m			17.0			17.10	Gravelly SAND: fine to coarse grained, grey and pale grey, gravel is fine to coarse grained sub-angular to sub-rounded; trace low plasticity clay.	M	MD				ELLIOT FORMATION	17.0
								-10.3			-10.44								
								18.0	SW										18.0
								-11.3											
					19.00m SPT 2,5,1 N=6 (0.45m REC) 19.45m			19.0			19.20	Sandy CLAY: medium plasticity, grey, sand is fine to coarse grained; with fine to coarse grained sub-angular to sub-rounded gravel.	w=PL	F					19.0
								-12.3	CI		19.40	Sandy GRAVEL: fine to coarse grained, sub-angular to sub-rounded, brown and grey, sand is fine to coarse grained; with low plasticity clay.	M	L - MD					
								20.0			-12.74								
						20.10m PP>500kPa		-13.3	GW										
					20.50m SPT 7,13,17 N=30 (0.45m REC) 20.95m			20.0			20.60	CLAY: high plasticity, pale brown and grey.	w=PL	H				RESIDUAL SOIL	20.0
						20.80m PP>500kPa		-14.3	CH		-13.94								
								21.0											21.0
					22.00m SPT 9,16,21 N=37 (0.45m REC) 22.45m			22.0			22.00	Sandy GRAVEL: fine to coarse grained, sub-angular to sub-rounded, grey, sand is fine to coarse grained.	M	D					22.0
						22.30m PP=300kPa 22.45m PP>500kPa		-15.3	GW		22.20	CLAY: high plasticity, orange-brown and pale grey, with fine grained sand.	w=PL	H					
								23.0	CH		-15.54								
								-16.3											23.0
					23.50m SPT 11,18,26 N=44 (0.45m REC) 23.95m			23.0			23.50	Sandy GRAVEL: fine to coarse grained, sub-angular to sub-rounded, grey, sand is fine to coarse grained.	M	D					
						23.80m PP>500kPa		-16.3	GW		-16.94	CLAY: high plasticity, orange-brown and grey, trace fine grained sand.	w=PL	H					
								24.0	CH										

Observations and Comments

Notes

Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 18/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 3 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435062.0 m
 North 7250140.0 m
 Elevation 6.66 m
 Datum MGA2020-56/AHD

Start Date 17/4/2024
 End Date 18/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier:

BH05

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)													
							23.90m PP>500kPa		24.0 -17.3				CLAY: high plasticity, orange-brown and grey, trace fine grained sand. (continued)	w=PL	H				RESIDUAL SOIL	
									24.70 -18.04	CH			CLAY: medium to high plasticity, orange-brown and grey, trace fine grained sand; (Extremely Weathered).						EXTREMELY WEATHERED MATERIAL	
									25.0 -18.3			25.10	Hole Terminated at 25.10 m Refusal							25.0
									26.0 -19.3											26.0
									27.0 -20.3											27.0
									28.0 -21.3											28.0
									29.0 -22.3											29.0
									30.0 -23.3											30.0
									31.0 -24.3											31.0
									32.0											

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 18/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 4 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435707.9 m
 North 7250276.3 m
 Elevation 8.98 m
 Datum MGA2020-56/AHD

Start Date 29/4/2024
 End Date 29/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH06**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
								0.0			0.20	TOPSOIL Sandy CLAY: medium to high plasticity, dark brown, sand is fine to medium grained; trace rootlets.	w=PL					TOPSOIL	
								0.95			8.78	Sandy CLAY: medium to high plasticity, dark brown to brown, sand is fine to coarse grained.		F				ALLUVIAL SOIL	
								1.0											
								1.50			1.70	1.50: Colour changes to pale grey							
								2.0			7.18	Clayey SAND: fine to coarse grained, grey to pale grey, clay is low plasticity. Sandy CLAY: medium plasticity, pale grey and brown, sand is fine to medium grained; (Extremely Weathered).	M	VD				EXTREMELY WEATHERED MATERIAL	
								2.50											
								3.0											
								4.0											
								4.50											
								5.0											
								5.50			5.50	Sandy CLAY: high plasticity, dark brown to brown, sand is fine to coarse grained; trace fine to coarse grained, sub-angular to sub-rounded gravel; (Extremely Weathered).							
								6.0			3.48								
								7.0											
								8.0											

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 29/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 1 of 3

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435707.9 m
 North 7250276.3 m
 Elevation 8.98 m
 Datum MGA2020-56/AHD

Start Date 29/4/2024
 End Date 29/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH06**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)													
								Not Observed	16.0 -7.0			-7.02	CLAY: medium to high plasticity, pale grey and red-brown, trace fine grained sand.	w=PL	St				RESIDUAL SOIL	
					16.50m SPT 2,3,6 N=9 (0.45m REC) 16.95m		16.70m PP=200kPa 16.80m PP=200kPa		17.0 -8.0			16.95	Hole Terminated at 16.95 m Target Depth							17.0
									18.0 -9.0											18.0
									19.0 -10.0											19.0
									20.0 -11.0											20.0
									21.0 -12.0											21.0
									22.0 -13.0											22.0
									23.0 -14.0											23.0
									24.0 -14.0											

Draft

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 29/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 3 of 3

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435855.2 m
 North 7250566.6 m
 Elevation 5.70 m
 Datum MGA2020-56/AHD

Start Date 26/4/2024
 End Date 26/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surlana Jurong Group
 Borehole Identifier:

BH08

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
								0.0 5.7			5.70	FILL Sandy CLAY: low to medium plasticity, dark brown, grey and pale grey, sand is fine to coarse grained; with fine to medium grained, sub-angular to sub-rounded gravel.	w<PL					FILL	
								0.50m SPT 1,3,1 N=4 (0.45m REC) 0.95m		CL									
								1.50m SPT 2,4,3 N=7 (0.45m REC) 1.95m		SP	1.60	FILL Gravelly SAND: fine to coarse grained, grey and dark brown, gravel is fine to coarse grained, sub-angular to sub-rounded.	D	F - St				ALLUVIAL SOIL	
								2.50m SPT 1,3,4 N=7 (0.45m REC) 2.95m	1.95m PP>500kPa	CI	4.00	Sandy CLAY: medium plasticity, brown mottled white, sand is fine to medium grained.	w<PL						
								3.50m SPT 3,4,5 N=9 (0.45m REC) 3.95m	2.70m PP=140kPa 2.80m PP=180kPa	CI-CH	2.50 3.20	CLAY: medium to high plasticity, dark brown, with fine to medium grained sand.							
								4.50m SPT 1,1,1 N=2 (0.45m REC) 4.95m	3.70m PP=300kPa 3.80m PP=300kPa	CH	3.50 2.20	CLAY: high plasticity, dark brown and dark grey, with fine to medium grained sand.	w=PL	St					
				U90				7.00m SPT HW/450mm (0.45m REC)	4.70m PP=150kPa 4.80m PP=140kPa		4.60 1.10	CLAY: medium plasticity, grey and dark grey, trace fine grained sand.		VS - S				MARINE SOIL	
									6.00m PP=90kPa	CI									
									7.30m PP=90kPa 7.40m PP=80kPa										

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 26/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 1 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435855.2 m
 North 7250566.6 m
 Elevation 5.70 m
 Datum MGA2020-56/AHD

Start Date 26/4/2024
 End Date 26/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surlana Jurong Group
 Borehole Identifier: **BH08**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)													
													CLAY: medium plasticity, grey and dark grey, trace fine grained sand. (continued)	w=PL	VS - S				MARINE SOIL	
					8.50m SPT HW/450mm (0.45m REC)		8.80m PP=110kPa 8.90m PP=110kPa						8.50: Trace fine to medium grained sand							
				U90																
							10.50m PP=430-450kPa													
					11.50m SPT 1,3,7 N=10 (0.45m REC) 11.95m							11.30 -5.60	CLAY: medium to high plasticity, grey to pale grey, with fine to medium grained sand.		St				ELLIOT FORMATION	
												11.95								
												12.10 -6.40	Sandy CLAY: medium to high plasticity, red-brown, sand is fine to coarse grained; trace fine to coarse grained gravel; (Extremely Weathered). Clayey SAND: fine to coarse grained, pale grey, clay is low to medium plasticity; trace fine to medium grained, sub-rounded gravel.	W	L			EXTREMELY WEATHERED MATERIAL ELLIOT FORMATION		
					13.00m SPT 1,2,2 N=4 (0.45m REC) 13.45m															
					14.50m SPT 4,5,4 N=9 (0.45m REC) 14.95m							14.80	Sandy CLAY: medium to high plasticity, pale brown, sand is fine to medium grained; (Extremely Weathered). Clayey SAND: medium to coarse grained, pale brown and pale grey, with fine to medium grained, sub-rounded gravel.	W	MD			EXTREMELY WEATHERED MATERIAL ELLIOT FORMATION		
					16.00m															

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 26/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 2 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435855.2 m
 North 7250566.6 m
 Elevation 5.70 m
 Datum MGA2020-56/AHD

Start Date 26/4/2024
 End Date 26/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surlana Jurong Group
 Borehole Identifier:

BH08

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology, Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
								16.0 -10.3				Clayey SAND: medium to coarse grained, pale brown and pale grey, with fine to medium grained, sub-rounded gravel. (continued)	W	MD				ELLIOT FORMATION	
								17.0 -11.3			17.20 -11.50	Gravelly SAND: fine to coarse grained, pale grey and pale brown, gravel is fine to coarse grained, sub-angular to sub-rounded; with low plasticity clay.							
								18.0 -12.3											
								19.0 -13.3			19.20 -13.50	Clayey SAND: fine to coarse grained, pale brown and pale grey, clay is low to medium plasticity; trace fine to medium grained, sub-angular to sub-rounded gravel. 19.60: Possible boulder							
								20.0 -14.3											
								21.0 -15.3											
								22.0 -16.3			22.10 -16.40	CLAY: high plasticity, pale grey.	w=PL	VSt				RESIDUAL SOIL	
								23.0 -17.3											
								23.50 -17.95					w=PL						

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal. For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 26/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 3 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435855.2 m
 North 7250566.6 m
 Elevation 5.70 m
 Datum MGA2020-56/AHD

Start Date 26/4/2024
 End Date 26/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH08**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation
					SPT (Recovered length)	DCP													
								24.0 -18.3				CLAY: high plasticity, pale grey. (continued)	w=PL	VSt				RESIDUAL SOIL	
								25.0 -19.3											25.0
								25.45m											
								25.30m PP=480kPa 25.40m PP=480kPa											
								26.0 -20.3											26.0
								26.50m											
								SPT 6, 10, 13 N=23 (0.45m REC) 26.95m											
								26.70m PP>500kPa 26.80m PP>500kPa		CH									27.0
								27.0 -21.3											
								28.0 -22.3				28.00: Colour changes to red-brown and pale grey							28.0
								28.00m											
								SPT 6, 10, 13 N=23 (0.45m REC) 28.45m											
								28.30m PP>500kPa 28.40m PP>500kPa											28.0
								29.0 -23.3											29.0
								29.50m											
								SPT 6, 10, 13 N=23 (0.45m REC) 29.95m											
								29.70m PP=480kPa 29.80m PP>500kPa			29.95								30.0
								30.0 -24.3				Hole Terminated at 29.95 m Target Depth							30.0
								31.0 -25.3											31.0
								32.0 -26.3											

Observations and Comments

Notes Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 26/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page 4 of 4

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435793.4 m
 North 7250637.0 m
 Elevation 5.81 m
 Datum MGA2020-56/AHD

Start Date 23/4/2024
 End Date 23/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH09**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing		Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation		
					SPT (Recovered length)	DCP														PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)	
								16.0 -10.2		GP	16.20	Sandy GRAVEL: fine to coarse grained, pale grey, red-brown, sand is fine to coarse grained; with low plasticity clay.	W	L					ELLIOT FORMATION		
											-10.39	Clayey SAND: fine to coarse grained, pale grey and red-brown, clay is low to medium plasticity; trace fine to medium grained, sub-angular to sub-rounded gravel.		MD						17.0	
								17.0 -11.2		SC											
								17.50m			17.50										
											-17.79	Sandy GRAVEL: fine to coarse grained, sub-angular to sub-rounded, pale grey, sand is fine to coarse grained; with low plasticity clay.								18.0	
								18.0 -12.2				Clayey SAND: fine to coarse grained, red-brown and brown, clay is low to medium plasticity; trace fine to coarse grained, sub-angular to sub-rounded gravel.									
								19.0 -13.2		SC											19.0
								19.00m			19.95										
												Hole Terminated at 19.95 m Target Depth									20.0
								20.0 -14.2													
								21.0 -15.2													
								22.0 -16.2													
								23.0 -17.2													
								24.0 -18.2													

Observations and Comments

Notes

Classifications compliant with AS1726-2017: Geotechnical Site Investigations unless otherwise noted. Lugeon: BS5930:1999
 Defect Log Abridged. Additional detail in digital dataset. For Vertical Holes: Angles reported in defects are relative to core normal.
 For Inclined Holes: Angles reported in defects are measured relative to core axis. Where beta angles are indicated, orientation of the core has been performed. Refer to explanatory notes for SMEC logs for details of abbreviations or basis of description.

Logged By CP Date 23/4/2024
 Approved By JY Date 17/5/2024
 Status 2 Page3 of 3

Geological & Engineering Log

Project Bundaberg East Levee
 Client Department of Housing QLD
 Site Bundaberg
 Job No 30034151

East 435797.5 m
 North 7250732.5 m
 Elevation 8.15 m
 Datum MGA2020-56/AHD

Start Date 24/4/2024
 End Date 24/4/2024

Contractor DTMR
 Rig Type Comacchio Geo 405
 Mounting Track

Inclination -90°
 Azimuth North
 Survey



Member of the Surbana Jurong Group
 Borehole Identifier: **BH10**

Method	Casing	Progress Water (Loss/Return)	Run (TCR) RQD	Sampling	Testing			Water Level & Inflow	Depth (m) Elevation	Graphic Log	USCS Code	Depth RL	Soil / Rock Material Description	Moisture Condition	Consistency Density	Alteration	Weathering	Rock Strength	Origin, Geology Unit, Other Testing & General Observations	Installation	
					SPT (Recovered length)	DCP	PP (kPa) VS (kPa) (P/R uncorrected) PID (ppm)														
									16.0 -7.8				Clayey SAND: fine to coarse grained, pale brown and pale grey, clay is low plasticity; with fine to medium grained, sub-angular to sub-rounded gravel. (continued)	W	MD					ELLIOT FORMATION	
									17.0 -8.8	SC											17.0
									17.50m			17.50									
												-9.35	Gravelly SAND: fine to coarse grained, pale grey and pale brown, gravel is fine to coarse grained, sub-angular to sub-rounded; with low plasticity clay.		L - MD						18.0
									18.0 -9.8												18.0
									19.0 -10.8	SP											19.0
									19.50m			19.95	Hole Terminated at 19.95 m Target Depth								20.0
									20.0 -11.8												20.0
									21.0 -12.8												21.0
									22.0 -13.8												22.0
									23.0 -14.8												23.0
									24.0 -15.8												24.0

Appendix C **SPT Photographs**



Photo 1: BH01 SPT01



Photo 2: BH01 SPT02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	1 of 74



Photo 3: BH01 SPT03



Photo 4: BH01 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	2 of 74



Photo 5: BH01 SPT05



Photo 6: BH01 SPT06


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	3 of 74



Photo 7: BH01 U01



Photo 8: BH01 SPT07


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	4 of 74



Photo 9: BH01 SPT08



Photo 10: BH01 SPT09


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	5 of 74



Photo 11: BH01 SPT10



Photo 12: BH01 SPT11


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	6 of 74



Photo 13: BH01 SPT12



Photo 14: BH01 SPT13


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	7 of 74



Photo 15: BH01 SPT14



Photo 16: BH01 SPT15


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	8 of 74



Photo 17: BH02 SPT01



Photo 18: BH02 SPT02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	9 of 74



Photo 19: BH02 SPT03



Photo 20: BH02 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	10 of 74



Photo 21: BH02 U01



Photo 22: BH02 SPT05


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	11 of 74



Photo 23: BH02 SPT06



Photo 2: 4BH02 SPT07



Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	12 of 74



Photo 25: BH02 SPT08



Photo 26: BH02 SPT09

Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	13 of 74




Photo 27: BH02 SPT10



Photo 28: BH02 SPT11



Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	14 of 74



Photo 29: BH02 SPT12



Photo 30: BH02 SPT13

Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	15 of 74




Photo 31: BH02 SPT14



Photo 32: BH02 SPT15


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	16 of 74



Photo 33: BH02 SPT16



Photo 34: BH02 SPT17


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	17 of 74



Photo 35: BH02 SPT18


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	18 of 74



Photo 36: BH03 SPT01



Photo 37: BH03 SPT02


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	19 of 74



Photo 38: BH03 SPT03



Photo 39: BH03 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	20 of 74



Photo 40: BH03 SPT05



Photo 41: BH03 SPT06


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	21 of 74



Photo 42: BH03 SPT07



Photo 43: BH03 SPT08


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	22 of 74



Photo 44: BH03 SPT09



Photo 45: BH03 SPT10


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	23 of 74



Photo 46: BH03 SPT11



Photo 47: B BH03 SPT12


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	24 of 74



Photo 48: BH03 SPT13



Photo 49: BH03 SPT14


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	25 of 74



Photo 50: BH03 SPT15



Photo 51: BH03 SPT16


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	26 of 74



Photo 52: BH04 SPT01



Photo 53: BH04 SPT02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	27 of 74



Photo 54: BH04 SPT03



Photo 55: BH04 SPT04


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	28 of 74



Photo 56: BH04 SPT05



Photo 57: BH04 U01


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	29 of 74



Photo 58: BH04 SPT06



Photo 59: BH04 SPT07


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	30 of 74



Photo 60: BH04 SPT08



Photo 61: BH04 U02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	31 of 74



Photo 62: BH04 SPT09



Photo 63: BH04 SPT10


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	32 of 74



Photo 64: BH04 SPT11



Photo 65: BH04 SPT12



Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	33 of 74



Photo 66: BH04 SPT13



Photo 67: BH04 SPT14

Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	34 of 74




Photo 68: BH04 SPT15


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	35 of 74



Photo 69: BH05 SPT01



Photo 70: BH05 SPT02


Date Taken:	-		Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	36 of 74



Photo 71: BH05 SPT03



Photo 72: BH05 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	37 of 74



Photo 73: BH05 SPT05



Photo 74: BH05 SPT06


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	38 of 74



Photo 75: BH05 SPT07



Photo 76: BH05 U01


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	39 of 74



Photo 77: BH05 SPT08



Photo 78: BH05 SPT09


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	40 of 74



Photo 79: BH05 SPT10



Photo 80: BH05 U02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	41 of 74



Photo 81: BH05 SPT11



Photo 82: BH05 SPT12


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	42 of 74



Photo 83: BH05 SPT1013



Photo 84: BH05 SPT14


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	43 of 74



Photo 85: BH05 SPT15



Photo 86: BH05 SPT16


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	44 of 74



Photo 87: BH06 SPT01



Photo 88: BH06 SPT02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	45 of 74



Photo 89: BH06 SPT03



Photo 90: BH06 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	46 of 74



Photo 91: BH06 SPT06



Photo 92: BH06 SPT06


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	47 of 74



Photo 93: BH06 SPT07



Photo 94: BH06 SPT08


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	48 of 74



Photo 95: BH06 SPT09



Photo 96: BH06 SPT10


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	49 of 74



Photo 97: BH08 SPT01



Photo 98: BH08 SPT03


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	50 of 74



Photo 99: BH08 SPT4



Photo 100: BH08 SPT05


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	51 of 74



Photo 101: BH08 U01



Photo 102: BH08 SPT06


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	52 of 74



Photo 103: BH08 SPT07



Photo 104: BH08 U02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	53 of 74



Photo 105: BH08 SPT08



Photo 106: BH08 SPT09


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	54 of 74



Photo 107: BH08 SPT10



Photo 108: BH08 SPT11


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	55 of 74



Photo 109: BH08 SPT12



Photo 110: BH08 SPT13


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	56 of 74



Photo 111: BH08 SPT14



Photo 112: BH08 SPT15


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	57 of 74



Photo 113: BH08 SPT16



Photo 114: BH08 SPT17


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	58 of 74



Photo 115: BH08 SPT18



Photo 116: BH08 SPT19


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	59 of 74



Photo 117: BH09 SPT01



Photo 118: BH09 SPT02


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	60 of 74



Photo 119: BH09 SPT03



Photo 120: BH09 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	61 of 74



Photo 121: BH09 SPT05



Photo 122: BH09 SPT06


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	62 of 74



Photo 123: BH09 SPT07



Photo 124: BH09 SPT08


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	63 of 74



Photo 125: BH09 SPT09



Photo 126: BH09 SPT10


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	64 of 74



Photo 127: BH09 SPT11



Photo 128: BH09 SPT12


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	65 of 74



Photo 129: BH09 SPT13



Photo 130: BH09 SPT14


Date Taken:	-	 SMEC Member of the Surlana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	66 of 74



Photo 131: BH09 SPT15

Photo 2: BH02 Setup


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	67 of 74



Photo 132: BH10 SPT01



Photo 133: BH10 SPT02


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	68 of 74



Photo 134: BH10 SPT03




Photo 135: BH10 SPT04


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	69 of 74



Photo 136: BH10 SPT05



Photo 137: BH10 SPT06


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	70 of 74



Photo 138: BH10 SPT07



Photo 139: BH10 SPT08


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	71 of 74



Photo 140: BH10 SPT09



Photo 141: BH10 SPT10


Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	72 of 74



Photo 142: BH10 SPT11



Photo 143: BH10 SPT13



Date Taken:	-	 <p>Member of the Surbana Jurong Group</p>	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	73 of 74



Photo 144: BH10 SPT14


Date Taken:	-	 Member of the Surbana Jurong Group	Client:	DHLGPPW		
Taken By:	CP		Project:	Bundaberg East Levee		
Checked By:	BY		Title:	Site Photographs		
			Project No:	30034151	Page:	74 of 74

Appendix D Piezocone Penetration Test

CONE PENETROMETER TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-01



Job Number : G24-03-09
 Test Date : 21/04/2024
 GPS Position : 56 J 435019, 7250107
 GPS Format : WGS 84
 Rig : Beryl
 Test Category : IGS-3S
 Predrill Depth : 0.00m
 Cone Stabilisation @ : 3m
 Dissipation Tests @ : 6.5m 10.m
 Terminated Due To : Equipment at Risk


Cone Number : S15CFIIP.S19568
 Calibration Date : 15/04/2024
 Cone Capacity : 100MPa
 Cone Diameter : 44.07mm
 Cone NAR : 0.785
 Tested By : Sean Gibson
 Checked By : Tony Hitchcock



CONE PENETROMETER TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-02



Job Number : G24-03-09
 Test Date : 19/04/2024
 GPS Position : 56 J 435099, 7250145
 GPS Format : WGS 84
 Rig : Beryl
 Test Category : IGS-3S
 Predrill Depth : 0.00m
 Cone Stabilisation @ : 0.7m
 Dissipation Tests @ : 8.5m 14m 19.41m
 Terminated Due To : Equipment at Risk


Cone Number : S15CFIIP.S19568
 Calibration Date : 15/04/2024
 Cone Capacity : 100MPa
 Cone Diameter : 44.07mm
 Cone NAR : 0.785
 Tested By : Sean Gibson
 Checked By : Tony Hitchcock



CONE PENETROMETER TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-03



Job Number : G24-03-09
 Test Date : 20/04/2024
 GPS Position : 56 J 435168, 7250146
 GPS Format : WGS 84
 Rig : Beryl
 Test Category : IGS-3S
 Predrill Depth : 0.00m
 Cone Stabilisation @ : 2.8m
 Dissipation Tests @ : 7m 15m 17.49m
 Terminated Due To : Equipment at Risk


Cone Number : S15CFIIP.S19568
 Calibration Date : 15/04/2024
 Cone Capacity : 100MPa
 Cone Diameter : 44.07mm
 Cone NAR : 0.785
 Tested By : Sean Gibson
 Checked By : Tony Hitchcock



CONE PENETROMETER TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-04



Job Number : G24-03-09
 Test Date : 21/04/2024
 GPS Position : 56 J 435214, 7250125
 GPS Format : WGS 84
 Rig : Beryl
 Test Category : IGS-3S
 Predrill Depth : 0.00m
 Cone Stabilisation @ : 1m
 Dissipation Tests @ : N/A
 Terminated Due To : Lifted Rig


Cone Number : S15CFIIP.S19568
 Calibration Date : 15/04/2024
 Cone Capacity : 100MPa
 Cone Diameter : 44.07mm
 Cone NAR : 0.785
 Tested By : Sean Gibson
 Checked By : Tony Hitchcock



CONE PENETROMETER TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-05



Job Number : G24-03-09
 Test Date : 23/04/2024
 GPS Position : 56 J 435335, 7250160
 GPS Format : WGS 84
 Rig : Beryl
 Test Category : IGS-3S
 Predrill Depth : 0.00m
 Cone Stabilisation @ : 1m, 8m
 Dissipation Tests @ : 9.2m
 Terminated Due To : Equipment at Risk


Cone Number : S15CFIIP.T.S22648
 Calibration Date : 23/02/2024
 Cone Capacity : 100MPa
 Cone Diameter : 43.98mm
 Cone NAR : 0.788
 Tested By : Sean Gibson
 Checked By : Tony Hitchcock



CONE PENETROMETER TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-06



Job Number : G24-03-09
 Test Date : 22/04/2024
 GPS Position : 56 J435818, 7250601
 GPS Format : WGS 84
 Rig : Beryl
 Test Category : IGS-3S
 Predrill Depth : 0.00m
 Cone Stabilisation @ : 2.3m
 Dissipation Tests @ : 9.5m
 Terminated Due To : Equipment at Risk

Cone Number : S15CFIIPT.S22648
 Calibration Date : 23/02/2024
 Cone Capacity : 100MPa
 Cone Diameter : 43.98mm
 Cone NAR : 0.788
 Tested By : Sean Gibson
 Checked By : Tony Hitchcock




Appendix E Pore Pressure Dissipation Test

PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-01
Depth: 6.5m



Tested By: Sean Gibson
 Test Duration: 2 Hours, 0 Minutes
 Test Date: 21/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-01
Depth: 10.5m



Tested By: Sean Gibson
 Test Duration: 15 Hours, 0 Minutes
 Test Date: 21/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-02
Depth: 8.5m



Tested By: Sean Gibson
 Test Duration: 1 Hours, 15 Minutes
 Test Date: 19/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-02
Depth: 14m



Tested By: Sean Gibson
 Test Duration: 3 Hours, 40 Minutes
 Test Date: 19/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-02
Depth: 19.41m



Tested By: Sean Gibson
 Test Duration: 14 Hours, 0 Minutes
 Test Date: 19/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-03
Depth: 7m



Tested By: Sean Gibson
 Test Duration: 3 Hours, 55 Minutes
 Test Date: 20/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-03
Depth: 15m



Tested By: Sean Gibson
 Test Duration: 14 Hours, 17 Minutes
 Test Date: 20/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
 Bundaberg East Levee Site Investigation
 Bundaberg QLD

CPT-03
 Depth: 17.49m



Tested By: Sean Gibson
 Test Duration: 0 Hours, 15 Minutes
 Test Date: 20/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.S19568


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-05
Depth: 9.2m



Tested By: Sean Gibson
 Test Duration: 22 Hours, 1 Minutes
 Test Date: 23/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.T.S22648


Termination Reason: Client Direction
 Special Notes: Nil



PORE PRESSURE DISSIPATION TEST RESULT

SMEC
Bundaberg East Levee Site Investigation
Bundaberg QLD

CPT-06
Depth: 9.5m



Tested By: Sean Gibson
 Test Duration: 0 Hours, 20 Minutes
 Test Date: 22/04/2024
 Job No: G24-03-09
 Cone: S15CFIIP.T.S22648

Termination Reason: Client Direction
 Special Notes: Nil



Appendix F **Vane Shear Test**



INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-01
(3.5 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435018, 7250106
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	3.50
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-01
(5 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435018, 7250106
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	5.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-01
(7 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435018, 7250106
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	7.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-01
(9 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435018, 7250106
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	9.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-01
(11 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435018, 7250106
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	11.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-01
(12 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435018, 7250106
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	12.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-02
(5.0 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435098, 7250144
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	5.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-02
(7.0 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435098, 7250144
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	7.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-02
(8.5 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435098, 7250144
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	8.50
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-02
(11.2 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435098, 7250144
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	11.20
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-02
(13 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435098, 7250144
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	13.00
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-02
(14.5 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435098, 7250144
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	14.50
TEST DATE	20/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-05
(4.5 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435334, 7250160
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	4.50
TEST DATE	24/04/2024
ROTATION RATE (°/min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-05
(6.0 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435334, 7250160
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	6.00
TEST DATE	24/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-05
(7.5 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435334, 7250160
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	7.50
TEST DATE	24/04/2024
ROTATION RATE (°/min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-05
(10.0 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435334, 7250160
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	10.00
TEST DATE	24/04/2024
ROTATION RATE (°/min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman





INSITU GEOTECH SERVICES
reducing geotechnical uncertainty


VANE SHEAR TEST

CPT-05
(11.0 m)

CLIENT	SMEC
PROJECT	Bundaberg East Levee
LOCATION	Bundaberg QLD
JOB NUMBER	G24-03-09
GPS POSITION	56 J 435334, 7250160
GPS FORMAT	WGS84

VANE TYPE	I-VANE
VANE NUMBER	231001V
CALIBRATION DATE	19/12/2023
VANE SIZE	50 x 100
VANE CONSTANT	1.964

TEST DEPTH (m)	11.00
TEST DATE	24/04/2024
ROTATION RATE ($^{\circ}$ /min)	6
TESTED BY	Sean Gibson
CHECKED BY	Mark Chapman



Appendix G **Geophysics Survey**

Appendix H **Laboratory Test Certificates**



Member of the Surbana Jurong Group

SMEC

Level 6, 480 St Pauls Terrace
Fortitude Valley, Queensland 4006

Phone: +61 7 4729 6727

Email: australia@smec.com

Redefining exceptional

Through our specialist expertise, we're challenging boundaries to deliver advanced infrastructure solutions.

www.smec.com